

### **ADDENDUM NO. 1**

# TOWN OF CUTLER BAY INVITATION TO BID (ITB) No. 25-06 SOIL REMEDIATION PROJECT FOR BLUE HERON PARK

Addendum No. 1 form shall be part of the original ITB No. 25-06 SOIL REMEDIATION PROJECT FOR BLUE HERON PARK document and modifies the original ITB as noted below:

### REVISION TO ORIGINAL ITB DOCUMENTS BELOW: "RED"

- The original Bid Form has been replaced with the revised Bid Form found in Addendum 1.
- The plans have been replaced with the revised plans found in Addendum 1.
- The Financial Statement has been removed from the ITB.

**Financial Statement:** 

[SPACE LEFT INTENTIONALLY BLANK]

# TOWN OF CUTLER BAY SOIL REMEDIATION PROJECT FOR BLUE HERON PARK ITB No. 25-06 29100 SW 97 Avenue Folio No. 36-6016-027-0010

### **BID FORM**

Please submit a **line-item bid** for (i) excavation, loading, transportation, and disposal of arsenic impacted soils above 2.1 parts per million to a properly licensed landfill facility approved by the Miami-Dade County Department of Regulatory and Economic Resources - Division of Environmental Resources Management (DERM), (ii) importation of clean fill from a limerock quarry located within Miami-Dade County, (iii) replacement of the existing walking path to include a change in alignment and material, and (iv) removal and replacement of existing hardscape features (including but not limited to pavilions, exercise equipment, benches, waste receptacles, and signs) in their existing locations, unless otherwise noted on the plans.

The construction will comply with the approved Source Removal / Soil Management Plan completed by Kimley Horn and Associates and approved, with modifications by Miami- Dade County DERM as stated in the letter dated May 15, 2025. Copies of manifests for loads leaving the site and signed copies from the accepting landfill will be required to be provided to the Town's oversight consultant, along with the Source Removal / Soil Management Plan acknowledgement form.

ITEM	DESCRIPTION	QUANTITY	UNITS	PRICE
MOBILIZATION	<ul> <li>Mobilization &amp; demobilization of forces and equipment</li> <li>Includes the construction of one (1) project sign that shall be displayed at the approaches to the project area. The intent is that the sign will be freestanding. The sign shall display on both sides the project name, City Logo, elected officials, and contact information. Shop drawings must be submitted for approval prior to ordering the project sign. Photos of the actual project sign must be submitted for approval prior to installation of the project signs.</li> </ul>	1	LS	\$
MAINTENANCE OF TRAFFIC	• Includes all pedestrian access maintenance. All crosswalks and sidewalks shall remain open and free of obstructions. Costs shall include the use of flagmen when needed.	1	LS	\$

GENERAL REQUIREMENTS	<ul> <li>Comply with Miami- Dade County DERM letter, dated May 15, 2025</li> <li>Comply with Source Removal / Soil Management Plan (Kimley Horn and Associates), dated April 15, 2025</li> <li>Dust control as per Source Removal / Soil Management Plan – Section 7.2</li> <li>Worker Health &amp; Safety Plan as per Source Removal / Soil Management Plan - Section 7.1</li> <li>Water truck</li> <li>Cover stockpile daily</li> </ul>	1	LS	\$
SURVEYING / AS-BUILT	Survey control monuments & benchmark	1	LS	\$
STORMWATER POLLUTION PREVENTION PLAN (SWPPP)	<ul> <li>Construction entrance</li> <li>Silt fence</li> <li>Sediment inlet barriers and turbidity barriers</li> <li>Geo fabric at construction entrance</li> <li>Notice of Intent (NOI) &amp; National Pollutant Discharge Elimination System (NPDES) permits</li> </ul>	1	LS	<b>\$</b>
CLEARING AND GRUBBING / DEMOLITION	<ul> <li>Includes the removal of stumps, roots, buried logs, brush, grass and other unsatisfactory materials in areas designated to be cleared and grubbed. Trees and other debris unavoidably falling outside the specified limits must be cut up, removed, and disposed of in a satisfactory manner. All trees not to be removed shall be preserved and protected from injury. Trees, stumps and brush shall be cut to a height of not more than 12-inches above the ground.</li> <li>On site burning of debris will not be allowed. All holes remaining after the grubbing operation in embankment areas shall have the sides broken down to flatten out the slopes, and shall be filled with acceptable material, moistened, and properly compacted in layers to the density required. The same construction</li> </ul>	1	LS	\$

	procedure shall be applied to all holes remaining after grubbing in excavation areas where the depth of holes exceeds the depth of the proposed excavation. Haul off materials to a DERM approved landfill.			
SITE RESTORATION	• Includes all materials, labor, and equipment necessary to perform site restoration work including swale restoration, sidewalk, roadway, or driveways impacted by any construction activity adjacent to project site including but not limited to concrete and base removal, striping removal, clearing and grubbing, utility installations, sidewalk installation, signpost relocations, etc.			
	• Includes, but is not limited to, new sod, landscaping, trees, excavation, backfill, grading, irrigation, driveway aprons, sidewalks, fences, pipes, curbs, and any other work required for project completion and acceptance. Any excavation, backfill, trench restoration, site restoration, and landscaping improvement costs referenced as part of other bid items shall be included in those bid items accordingly. Restoration other than or in addition to what is indicated by the plans, specifications, and defined herein will be considered incidental to the construction and the costs of this incidental restoration should be included in the cost of the project.	1	LS	\$
	The Contractor shall include the costs associated with a preconstruction video to confirm existing conditions. Any damage not confirmed by preconstruction video will be repaired at no additional cost to the City.			
	Includes replacement of all existing hardscape features not limited to pavilions, exercise equipment, benches, waste receptacles, and signs, in their existing locations unless otherwise noted on the plans.			

TEMPORARY CONSTRUCTION FENCE	Refer to Demolition Plan	5,500	LF	\$
EARTHWORK – OFFSITE	<ul> <li>Excavate muck</li> <li>Haul off muck to DERM approved landfill</li> <li>Final grading as per Source Removal / Soil Management Plan</li> </ul>	17,000	CY	\$
EARTHWORK – ONSITE	<ul> <li>Clean backfill being imported to the Site must comply with DERM Guidance 7H – Soil Reuse Guidance for Miami-Dade County, Revised January 2024, per the Source Removal / Soil Management Plan- Section 4.4</li> <li>Final grading as per Source Removal / Soil Management Plan and Restoration Plan</li> <li>Weight tickets of clean fill from an approved DERM facility will be required to be submitted to the Town's consultant for tracking purposes.</li> </ul>	31,000	CY	\$
8-FT FLEXI-PAVE PATH	<ul> <li>Includes all costs associated with installing flexi-pave walking paths including base and subgrade material and installation.</li> </ul>	3,300	SY	\$
CONCRETE SIDEWALK AND EXERCISE EQUIPMENT PADS (4 IN)	<ul> <li>Includes all costs associated with installing concrete pavements to include concrete sidewalks, driveways, and aprons up to 4" thick including base and subgrade material and installation.</li> </ul>	180	SY	\$
PAVILION SLAB CONCRETE (4 IN WITH REBAR)	Includes all costs associated with installing concrete slabs for pavilion installation, including but not limited to rebar, site preparation, and compaction.	150	SY	\$
SMALL PAVILION SHELTER	<ul> <li>Includes all furnishings, delivery, installation, and maintenance of proposed pavilion shelters. Contractor is responsible for the installation of the equipment per manufacturer's specifications.</li> </ul>	2	EA	\$

PALM TREE REMOVAL	Refer to Tree Disposition Plan	4	EA	\$
TREE PROTECTION ZONE	<ul> <li>Refer to Tree Disposition Plan</li> <li>Refer to Source Removal/Soil Management Plan</li> <li>Engineering Controls</li> <li>Comply with Miami- Dade DERM letter dated May 15, 2025: "DERM does not require the backfill material to be compacted, as described in section 4.4 Clean Backfill Material and Management, except within the "Tree Protection Zones" where contaminated soil has been proposed to remain in-place and covered with a 6-mil or greater impermeable liner covered by a minimum of one foot of clean backfill."</li> </ul>	1	LS	\$
ROOT BARRIER	Refer to Restoration Plan	1,500	LF	\$
ST. AUGUSTINE SOD	<ul> <li>Sod, including topsoil</li> <li>Contractor responsible for watering sod until establishment.</li> </ul>	21,000	SY	\$
PAYMENT & PERFORMANCE BOND	• Pursuant to and in accordance with Section 255.05, Florida Statutes, the Contractor shall obtain and thereafter at all times during the performance of the Work maintain a separate performance bond and labor and material payment bond for the Work, each in an amount equal to one hundred percent (100%) of the Contract.	1	LS	\$
ALLOWANCES	Project allowances	1	LS	\$75,000.00
T	OTAL BID PRICE			\$

BASE BID AMOUNT:	\$			
BASE BID AMOUNT (IN	WORDS):			

# TOWN OF CUTLER BAY BLUE HERON PARK

LOCATION CUTLER BAY, FLORIDA



### PROJECT TEAM

TOWN OF CUTLER BAY 10720 CARIBBEAN BOULEVARD, SUITE 105

CUTLER BAY, FLORIDA 33189 (305) 234-4262 CONTACT: RALPH CASALS

SURVEYOR HADONNE CORP. 1985 NW 88TH COURT, SUITE 101 DORAL, FLORIDA 33172 (305) 266-1188 CONTACT: ABRAHAM HADAD

## COMMUNITY OFFICIALS

VICE MAYOR COUNCIL MEMBER **COUNCIL MEMBER** COUNCIL MEMBER

MICHAEL CALLAHAN ROBERT "BJ" DUNCAN SUZY LORD RICHARD RAMIREZ

**CIVIL ENGINEER** 

(954) 535-5100

KIMLEY-HORN AND ASSOCIATES, INC.

8201 PETERS ROAD, SUITE 2200

CONTACT: STEFANO VIOLA, P.E.

PLANTATION, FLORIDA 33324



She	eet List Table
Sheet Number	Sheet Title
C000.0	COVER SHEET
C100.0	GENERAL NOTES
C200.0	DEMOLITION AND EROSION CONTROL PLAN
C200.1	DEMOLITION AND EROSION CONTROL PLAN
C200.2	DEMOLITION AND EROSION CONTROL PLAN
C200.3	DEMOLITION AND EROSION CONTROL PLAN
C201.0	DEMOLITION AND EROSION CONTROL NOTES AND DETAILS
C300.0	RESTORATION PLAN
C300.1	RESTORATION PLAN
C300.2	RESTORATION PLAN
C300.3	RESTORATION PLAN
C300.4	CROSS SECTIONS
C301.0	RESTORATION DETAILS
C301.1	RESTORATION DETAILS
C301.2	RESTORATION DETAILS
L1.00	TREE DISPOSITION PLAN
L1.01	TREE DISPOSITION PLAN
L1.02	TREE DISPOSITION PLAN
L1.03	TREE DISPOSITION PLAN
L1.04	TREE DISPOSITION PLAN

Shoot List Table

**VICINITY MAP** 1" = 250'

PREPARED BY: Kimley» Horn

THE PRESENCE OF GROUNDWATER SHOULD BE ANTICIPATED. CONTRACTOR'S BID SHALL INCLUDE CONSIDERATION FOR ADDRESSING THIS ISSUE AND OBTAINING ALL NECESSARY PERMITS

ALL ELEVATIONS SHOWN ON THESE PLANS . BASED ON THE NGVD 29. TO CONVERT ELEVATIONS TO NAVD 88, SUBTRACT 1.52'.



SHEET NUMBER C000.0

ITB No. 25-06 Addendum No. 1

Page 7 of 26

SHEE COVER

> ARED FOR CUTLE OF.

A. GENERAL

. ALL WORK FOR THIS PROJECT SHALL BE COMPLETED WITHIN AND FROM EXISTING

RIGHT OF WAY. COUNTY IN THESE NOTES REFERS TO THE MIAMI-DADE COUNTY, CITY OR TOWN IN THESE NOTES REFERS TO THE TOWN OF CUTLER BAY. STATE IN THESE NOTES REFERS TO THE STATE OF FLORIDA.

3. THE FDOT INDICES REFERRED TO IN THE DRAWINGS AND NOTES REFERS TO FLORIDA DEPARTMENT OF TRANSPORTATION (FDOT) STANDARD PLANS FOR ROAD AND BRIDGE CONSTRUCTION AND FDOT DESIGN STANDARDS LATEST EDITION.

4. ALL WORK AND MATERIALS SHALL CONFORM TO THE LATEST STANDARDS, CODES, REGULATIONS AND SPECIFICATIONS OF THE CITY, COUNTY, STATE, AND FEDERAL CODES WHERE APPLICABLE

5. THE CONTRACTOR SHALL BE REQUIRED TO COMPLY WITH FEDERAL, STATE, COUNTY, AND CITY LAWS, CODES, ORDINANCES AND REGULATIONS.

6. IN THE EVENT OF A CONFLICT BETWEEN THE GENERAL NOTES AND CONSTRUCTION SPECIFICATIONS IN THESE PLANS AND THE CONTRACT DOCUMENTS AND SPECIFICATIONS IN THE SPECIFICATIONS BOOKLET THE CONTRACTOR SHALL SUBMIT WRITTEN REQUEST FOR CLARIFICATION TO THE ENGINEER

7. ALL HANDICAP ACCESSIBLE ACCESS TO CONFORM WITH THE REQUIREMENTS OF THE AMERICANS WITH DISABILITIES ACT AND LOCAL, STATE, AND FEDERAL CODES, LATEST

8. THE CONTRACTOR IS REQUIRED TO OBTAIN ALL APPLICABLE CONSTRUCTION PERMITS PRIOR TO START OF CONSTRUCTION. THE CONTRACTOR SHALL APPLY FOR AND PROCURE ALL PERMITS AND LICENSES, PAY ALL APPLICABLE CHARGES, TAXES, ROYALTIES & FEES, AND GIVE ALL NOTICES NECESSARY TO COMPLETE THIS PROJECT.

9. RADII DIMENSIONS AND ELEVATIONS ARE TO BE EDGE OF PAVEMENT AND FINISH GRADE UNLESS NOTED OTHERWISE.

10. IF ABANDONED GAS, WATER, AND SEWER SERVICE LATERALS ARE ENCOUNTERED DURING EXCAVATION, THE SECTION IN THE EXCAVATED ENVELOPE WILL BE REMOVED AND THE STUB ON THE SIDE CONNECTED TO THE MAIN WILL BE CAPPED, PLUGGED OR OTHERWISE SEALED.

11. CONTRACTOR TO MAINTAIN ACCESS TO BUSINESS AND RESIDENTIAL LOCATIONS BY NORMAL MEANS AND METHODS, I.E. TEMPORARY STEEL PLATES, LIMEROCK, ETC. ALL ASSOCIATED COST TO BE INCLUDED IN M.O.T. PAY ITEM.

12. ITEMS IN CONFLICT WITH DESIGN SUCH AS EXISTING CURBS AND GUTTERS, SIDEWALKS, DRAINAGE STRUCTURES PAVEMENT AND BASE AND EXCESS EXCAVATIONS ARE TO BE REMOVED BY CONTRACTOR AND DISPOSED OF IN A LEGAL AND PROPER MANNER AWAY FROM THE JOB SITE AT THE CONTRACTOR'S EXPENSE UNLESS THE

ITEMS ARE TO BE REUSED ON THE PROJECT 13. EXCESS MATERIAL REMOVED BY THE CONTRACTOR WILL BE DISPOSED OF IN AREAS PROVIDED BY THE CONTRACTOR.

14. THE INFORMATION PROVIDED IN THESE PLANS IS TO ASSIST THE CONTRACTOR IN ASSESSING THE NATURE AND EXTENT OF THE CONDITIONS WHICH MAY BE ENCOUNTERED DURING THE COURSE OF THE WORK. ALL CONTRACTORS ARE DIRECTED, PRIOR TO BIDDING, TO CONDUCT ANY INVESTIGATIONS THEY DEEM NECESSARY TO ARRIVE AT THEIR OWN CONCLUSIONS REGARDING THE ACTUAL CONDITIONS THAT WILL BE ENCOUNTERED AND UPON WHICH THEIR BIDS WILL BE BASED. IT IS THE CONTRACTOR'S RESPONSIBILITY TO INVESTIGATE SITE CONDITIONS OF THE PROJECT AND FULLY SATISFY THEMSELVES OF BOTH THE SURFACE AND SUBSURFACE CONDITIONS AND BASE THEIR PRICING ACCORDINGLY. GEOTECHNICAL REPORT IS INCLUDED IN THE CONTRACT DOCUMENTS

15. CONTRACTOR SHALL PRESERVE ALL STREET SIGNS, BENCHES, TRAFFIC CONTROL SIGNS, LANDSCAPING, ETC. WHEN DIRECTED BY THE ENGINEER, THE CONTRACTOR SHALL REINSTALL OR DELIVER SAID PUBLIC PROPERTY TO THE COUNTY.

16. THE CONTRACTOR SHALL TAKE SPECIAL NOTE OF ANY SPECIAL EQUIPMENT SHORING, SHEETING OR OTHER PROCEDURES NECESSARY TO PROTECT ADJACENT PROPERTY, EITHER PUBLIC OR PRIVATE, DURING EXCAVATION OF SUBSOIL MATERIAL OR DURING THE FILLING OF ANY AREA, OR FOR ANY AREA, OR FOR ANY OPERATION DURING CONSTRUCTION SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND PROVIDED AT NO ADDITIONAL COST TO THE OWNER.

17. APPARENT ERRORS, DISCREPANCIES, OR OMISSIONS ON THE DRAWINGS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER OF RECORD IMMEDIATELY.

18. THE AMOUNT OF EACH OF THE MATERIALS PROVIDED IS THE ESTIMATED AMOUNT REQUIRED TO COMPLETE THE JOB. THESE QUANTITIES ARE ESTIMATED ONLY AND IT IS THE CONTRACTOR'S RESPONSIBILITY TO COMPLETE THE JOB IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. SHOULD ADDITIONAL MATERIALS BE REQUIRED THEY WILL BE PAID FOR AT THE CONTRACT UNIT PRICES AS DESCRIBED IN THE BID DOCUMENTS.

19. THE CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION OF ALL UTILITIES THAT REMAIN IN PLACE.

20. ALL ROAD CROSSINGS ARE OPEN CUT UNLESS OTHERWISE NOTED ON THE DRAWINGS. 21. THE CONTRACTOR SHALL REPLACE ALL PAVING, STABILIZING EARTH, DRIVEWAYS, SIDEWALKS, ETC. WITH THE SAME TYPE OF MATERIAL THAT WAS REMOVED DURING CONSTRUCTION OF AS DIRECTED BY THE ENGINEER.

22. THE CONTRACTOR SHALL NOT ENCROACH INTO PRIVATE PROPERTY WITH PERSONNEL, MATERIAL OR EQUIPMENT WITHOUT OBTAINING WRITTEN PERMISSION FROM THE OWNER. 23. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DAMAGE. REMOVAL OR MODIFICATION ACCIDENTALLY OR PURPOSELY, CAUSED TO ANY IRRIGATION SYSTEMS, PRIVATE OR PUBLIC WITHIN THE PROJECT LIMITS. THE COSTS TO REPLACE, REMOVE OR MODIFY IRRIGATION PIPES, SPRINKLER HEADS OR OTHER PERTINENT APPURTENANCES SHALL BE CONSIDERED INCIDENTAL TO AND SHALL BE INCLUDED IN THE OTHER ITEMS OF

OF THE CONTRACTOR. 24. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE INTEGRITY OF AND MAKING THE REPAIRS OF EXISTING PAVEMENT, PIPES, CONDUITS, CURBS, CABLES, TREES, SOD, LANDSCAPE ITEMS, ETC. WHETHER OR NOT SHOWN ON THE PLANS DAMAGED AS A RESULT OF THE CONTRACTORS OPERATIONS AND/OR THOSE OF THEIR SUBCONTRACTORS. CONTRACTOR SHALL REPORT ANY DAMAGE TO SIDEWALK, DRIVEWAY, ETC., PRIOR TO BEGINNING WORK IN ANY AREA.

RELATED WORK. ALL COSTS DUE TO DAMAGE SHALL BE THE SOLE RESPONSIBILITY

25. CONTRACTOR IS RESPONSIBLE TO REMOVE AND REINSTALL ALL BRICK OR PAVER DRIVEWAYS IMPACTED BY CONSTRUCTION, REPAIR OR REPLACE ALL ASPHALT, CONCRETE, OR STAMPED CONCRETE DRIVEWAYS IMPACTED BY CONSTRUCTION. ALL COSTS ASSOCIATED WITH THIS WORK SHALL BE INCLUDED AS PART OF THE OVERALL

26. THE CONTRACTOR SHALL RESTORE OR REPLACE, WHEN AND AS DIRECTED BY THE ENGINEER, ANY PUBLIC OR PRIVATE PROPERTY DAMAGED BY HIS/HER WORK, EQUIPMENT, EMPLOYEES OR THOSE OF HIS SUBCONTRACTORS TO A CONDITION AT LEAST EQUAL (DETERMINED BY THE ENGINEER OF RECORD) TO THAT EXISTING IMMEDIATELY PRIOR TO THE BEGINNING OF OPERATIONS.

27. CONTRACTOR SHALL ADJUST ALL EXISTING SURFACE FEATURES SUCH AS EXISTING FRAMES, GRATES, MANHOLE COVERS, UTILITY VALVE BOXES, MONITORING WELLS, ECT. TO MATCH PROPOSED GRADES.

28. ALL INSTALLATIONS WITHIN MIAMI-DADE COUNTY JURISDICTION RIGHTS OF WAY SHALL BE IN CONFORMITY WITH THE MIAMI-DADE COUNTY HIGHWAY CONSTRUCTION &

ENGINEERING DIVISION "MINIMUM STANDARDS." 29. THE VILLAGE OF PALMETTO BAY SHALL RECEIVE A COPY OF ALL REQUIRED DENSITY REPORTS, AS-BUILTS, AND SHOP DRAWINGS OF THE PROJECT.

CONSTRUCTION SAFETY

1. ALL CONSTRUCTION SHALL BE DONE IN A SAFE MANNER SPECIFICALLY, THE RULES AND REGULATIONS OF THE OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION

BE STRICTLY OBSERVED. C. TRENCH SAFETY ACT

(OSHA) AND THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (MUTCD) SHALL

1. CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLIANCE WITH THE STATE OF FLORIDA TRENCH SAFETY ACT.

2. WHERE EXCAVATIONS TO A DEPTH IN EXCESS OF FIVE FEET (5') ARE REQUIRED, THE CONTRACTOR SHALL INCLUDE THE FOLLOWING INFORMATION IN THE BID:

2.1. A REFERENCE TO THE TRENCH SAFETY STANDARDS THAT WILL BE IN EFFECT

DURING THE PERIOD OF CONSTRUCTION OF THE PROJECT 2.2. WRITTEN ASSURANCES BY THE CONTRACTOR PERFORMING THE TRENCH EXCAVATION THAT SUCH CONTRACTOR WILL COMPLY WITH THE APPLICABLE

TRENCH SAFETY STANDARDS 2.3. A SEPARATE ITEM IDENTIFYING THE COST OF COMPLIANCE WITH THE APPLICABLE TRENCH SAFETY STANDARDS. WHEN A BID IS NOT SUBMITTED, THE CONTRACTOR SHALL SUBMIT THE INFORMATION LISTED IN ITEM 2 ITO THE ENGINEER PRIOR TO STARTING WORK.

SURVEY DATA ALL ELEVATIONS ON THE PLANS OR REFERENCED IN THE SPECIFICATIONS ARE BASED ON NATIONAL GEODETIC VERTICAL DATUM (NGVD) OF 1929.

2. ALL EXISTING CONTROL POINTS AND/OR REFERENCE MARKERS SHALL BE RAISED TO FINAL GRADE. THESE POINTS AND REFERENCE MARKERS SHALL BE LOCATED AND NOTED ON THE AS-BUILTS.

3. THE LOCATION OF EXISTING RIGHT-OF-WAY LINES, CENTERLINES, ROADWAY PAVEMENT, UTILITIES, TREES AND OTHER PHYSICAL ABOVE-GROUND FEATURES SHOWN ON THE PLANS WERE TAKEN FROM THE SPECIFIC PURPOSE SURVEYS PREPARED BY:

> 1985 NW 88TH COURT, SUITE 101 DORAL, FLORIDA 33172 PHONE: 305-266-1188

CONTACT: ABRAHAM HADAD 4. ALL STATIONS AND OFFSETS ARE REFERENCED TO BASELINE OF

SURVEY/CONSTRUCTION BASELINE 5. EXISTING SECTION CORNERS AND 1/4 SECTION CORNERS, AND OTHER LAND MARKERS OR MONUMENTS LOCATED WITHIN PROPOSED CONSTRUCTION ARE TO BE REFERENCED BY THE CONTRACTOR PRIOR TO CONSTRUCTION AND REPLACED IF DISTURBED BY THE CONTRACTOR'S SURVEY OR UNDER THE DIRECTION OF A REGISTERED LAND SURVEYOR LICENSED IN THE STATE OF FLORIDA

ANY NGVD - 1929 MONUMENT WITHIN THE LIMITS OF CONSTRUCTION IS TO BE PROTECTED. IF IN DANGER OF DAMAGE, NOTIFY:

> GEODETIC INFORMATION CENTER ATTN: MARK MAINTANENCE SECTION N/CG-162 6001 EXECUTIVE BLVD. ROCKVILLE, MARYLAND 20852

PRECONSTRUCTION RESPONSIBILITIES

PHONE: 301-443-8319

UPON RECEIPT OF THE "NOTICE TO PROCEED", THE CONTRACTOR SHALL CONTACT THE ENGINEER OF RECORD AND ARRANGE A PRE-CONSTRUCTION CONFERENCE TO INCLUDE THE ALL INVOLVED GOVERNMENTAL AGENCIES, UTILITY OWNERS, AND THE ENGINEER OF RECORD, AND HOLD THE MANDATORY PRE-CONSTRUCTION CONFERENCE AFTER ISSUANCE OF THE CONTRACT'S "NOTICE TO PROCEED" BUT BEFORE THE ACTUAL CONSTRUCTION DATE. CONTRACTOR MAY NOT BEGIN WORK BEFORE ACTUAL CONSTRUCTION DATE.

2. THE CONTRACTOR SHALL OBTAIN A SUNSHINE CERTIFICATION NUMBER AT LEAST 48 HOURS PRIOR TO BEGINNING ANY EXCAVATION.

PRIOR TO BEGINNING CONSTRUCTION THE CONTRACTOR SHALL VERIFY THE SIZE, LOCATION ELEVATION, AND MATERIAL OF ALL EXISTING UTILITIES WITHIN THE AREA OF CONSTRUCTION.

EXISTING UTILITY LOCATION SHOWN ON THESE PLANS ARE APPROXIMATE. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR THE ACCURACY OF EXISTING UTILITIES SHOWN OR FOR ANY EXISTING UTILITIES NOT SHOWN.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR DAMAGE TO ANY EXISTING UTILITIES FOR WHICH IT FAILS TO REQUEST LOCATIONS FROM THE UTILITY OWNER. THE CONTRACTOR IS RESPONSIBLE AS WELL FOR DAMAGE TO ANY EXISTING UTILITIES WHICH ARE PROPERLY LOCATED

IF UPON EXCAVATION, AN EXISTING UTILITY IS FOUND TO BE IN CONFLICT WITH THE PROPOSED CONSTRUCTION OR TO BE OF A SIZE OR MATERIAL DIFFERENT FROM THAT SHOWN ON THE PLANS. THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE ENGINEER 7. EXISTING UTILITIES SHALL BE MAINTAINED IN SERVICE DURING CONSTRUCTION UNLESS

OTHERWISE APPROVED BY THE UTILITY OWNER. 8. THE CONTRACTOR SHALL COORDINATE WITH UTILITIES TO ARRANGE RELOCATION AND TEMPORARY SUPPORT OF UTILITY FEATURE ETC. AS NECESSARY TO COMPLETE THE

9. THE UTILITY COMPANIES SHALL BE NOTIFIED BY THE CONTRACTOR TWO (2) BUSINESS DAYS IN ADVANCE OF ANY EXCAVATION INVOLVING THEIR UTILITIES SO THAT A

COMPANY REPRESENTATIVE CAN BE PRESENT. 10. THE CONTRACTOR IS TO USE CAUTION WHEN WORKING IN OR AROUND AREAS OF OVERHEAD TRANSMISSION LINES OR UNDERGROUND UTILITIES.

11. SHOULD DEWATERING BE NEEDED, CONTRACTOR TO INCLUDE IN BID. ALL APPLICABLE CONTRACTOR TO INCLUDE FABRICATION, INSTALLATION, MAINTENANCE AND REMOVAL OF TWO (2) PROJECT SIGNS. SIGN LETTERING AND PLACEMENT TO BE REVIEWED BY TOWN PRIOR TO PLACEMENT.

12. STAGING AND STORAGE TO BE COORDINATED WITH TOWN PRIOR TO COMMENCEMENT OF CONSTRUCTION.

TEMPORARY FACILITIES

A.TEMPORARY UTILITIES

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO ARRANGE OR SUPPLY TEMPORARY WATER SERVICE, SANITARY FACILITIES, AND ELECTRICITY TO ITS EMPLOYEES AND SUBCONTRACTORS FOR THEIR USE DURING CONSTRUCTION. TRAFFIC REGULATION

MAINTENANCE OF TRAFFIC IN THE PUBLIC RIGHT-OF-WAY SHALL BE IN ACCORDANCE WITH THE MUTCD. A MAINTENANCE OF TRAFFIC PLAN MUST BE APPROVED BY BY THE GOVERNMENTAL ENGINEERING DIVISION HAVING JURISDICTION FOR THE SECTION OF ROADWAY BEFORE STARTING WORK IN THE PUBLIC RIGHT-OF-WAY.

2. ALL OPEN TRENCHES AND HOLES ADJACENT TO ROADWAYS OR WALKWAYS SHALL BE PROPERLY MARKED AND BARRICADED TO ASSURE THE SAFETY OF BOTH VEHICULAR AND PEDESTRIAN TRAFFIC.

NO TRENCHES OR HOLES NEAR WALKWAYS OR IN ROADWAYS OR THEIR SHOULDERS ARE TO BE LEFT OPEN DURING NIGHTTIME HOURS WITHOUT EXPRESS PERMISSION OF THE TOWN.

C. TEMPORARY FACILITIES

1. THE CONTRACTORS ON-SITE EQUIPMENT, STOCK PILED MATERIAL, AND SUPPLIES SHALL BE KEPT IN A SECURE, FENCED AND LOCKED WHEN CONTRACTOR IS NOT SUPERVISING THE STAGING OR LAY DOWN AREA. STAGING AND MATERIAL STORAGE SHALL NOT BE CONDUCTED ON ABUTTING PRIVATE

PROPERTY OR PUBLIC RIGHT-OF-WAY WITHOUT APPROVAL FROM THE TOWN OF MIAMI LAKES. 3. CONTRACTORS SHALL CONSTRUCT AND MAINTAIN TEMPORARY STREET LIGHTING AS REQUIRED TO LIGHT THE CONSTRUCTION PROJECT LIMITS AT ALL TIMES TO AT LEAST THE SAME LIGHTING INTENSITY LEVELS AS WAS EXISTING PRIOR TO THE START OF

CONSTRUCTION. ALL COSTS ASSOCIATED WITH CONSTRUCTION AND MAINTAINING LIGHTING TO BE INCLUDED IN M.O.T. PAY ITEM. 4. THE CONTRACTOR SHALL COORDINATE SELECTION AND REVIEW OF ANY PROPOSED STAGING AREAS ASSOCIATED WITH THIS PROJECT WITH THE TOWN OF MIAMI LAKES.

PROJECT CLOSEOUT

CLEANING UP

DURING CONSTRUCTION. THE PROJECT SITE AND ALL ADJACENT AREAS SHALL BE MAINTAINED IN A NEAT AND CLEAN MANNER. UPON FINAL CLEAN UP. THE PROJECT SITE SHALL BE LEFT CLEAR OF ALL SURPLUS MATERIAL OR TRASH, THE PAVED AREAS SHALL BE SWEPT BROOM CLEAN.

THE CONTRACTOR SHALL RESTORE OR REPLACE, WHEN AND AS DIRECTED BY THE ENGINEER OR THOSE OF ITS SUBCONTRACTORS TO A CONDITION AT LEAST EQUAL OR

BETTER TO THE EXISTING CONDITION IMMEDIATELY PRIOR TO THE BEGINNING OF OPERATIONS. TO THIS END, THE CONTRACTOR SHALL DO ALL NECESSARY HIGHWAY OR DRIVEWAY, WALK AND LANDSCAPING WORK, SUITABLE MATERIALS AND METHODS SHALL BE USED FOR SUCH RESTORATION

WHERE MATERIAL OR DEBRIS HAS WASHED OR FLOWED INTO OR BEEN PLACED IN WATER COURSES, DITCHES, DRAINS, CATCH BASINS, OR ELSEWHERE AS A RESULT OF THE CONTRACTOR'S OPERATIONS, SUCH MATERIAL OR DEBRIS SHALL BE REMOVED AND SATISFACTORILY DISPOSED OF DURING PROGRESS OF THE WORK. AND THE AREA KEPT IN A CLEAN AND NEAT CONDITION

4. UPON COMPLETION OF THE PROPOSED DRAINAGE WORK, THE CONTRACTOR SHALL CLEAN THE NEW SYSTEM, REMOVE ALL POLLUTION CONTROL DEVICES FROM THE NEW AND EXISTING SYSTEM, AND CLEAN THE EXISTING STRUCTURES AND DRAINAGE SYSTEM AT NO ADDITIONAL COST TO THE OWNER.

THE CONTRACTOR IS RESPONSIBLE FOR CLEANING OF ALL OF THE EXISTING DRAINAGE SYSTEM AFFECTED BY THE CONSTRUCTION WITHIN THE RIGHT-OF-WAY UPON COMPLETION OF THE PROJECT.

B. PROJECT RECORD DOCUMENTS

THE CONTRACTOR SHALL MAINTAIN ACCURATE AND COMPLETE RECORDS OF WORK ITEMS COMPLETED.

2. ALL "AS-BUILT" INFORMATION SUBMITTED TO THE ENGINEER SHALL BE SUFFICIENTLY ACCURATE, CLEAR AND LEGIBLE TO SATISFY THE ENGINEER THAT THE INFORMATION PROVIDES A TRUE REPRESENTATION OF THE IMPROVEMENTS CONSTRUCTED. UPON COMPLETION OF CONSTRUCTION, THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER OF RECORD COMPLETE SETS OF "AS-BUILT" CONSTRUCTION DRAWINGS SIGNED AND SEALED BY A FLORIDA CERTIFIED PROFESSIONAL LAND SURVEYOR) AS REQUIRED FOR SUBMITTAL AND APPROVAL. THESE DRAWINGS SHALL BE MARKED TO SHOW "AS-BUILT" CONSTRUCTION CHANGES AND DIMENSIONED LOCATIONS AND ELEVATIONS OF ALL IMPROVEMENTS AND SHALL BE SIGNED AND SEALED BY A REGISTERED LAND SURVEYOR

4. THE COST OF SIGNED AND SEALED AS-BUILTS AND CADD FILES SHALL BE INCLUDED IN THE COST OF THE OVERALL BID.

C. SOIL MANAGEMENT PLAN

DETAILS AND REQUIREMENTS.

1. CONTRACTOR SHALL UTILIZE THE HEALTH AND SAFETY PLAN (HASP) THAT HAS BEEN REVIEWED AND CERTIFIED BY A CERTIFIED INDUSTRIAL HYGIENIST (CIH). THE HASP CONTAINS THE FOLLOWING INFORMATION: THE EXPECTED CONTAMINANTS OF CONCERN, EMERGENCY RESPONSES FOR WORKERS EXPOSED, AND LOCATION OF CLOSEST MEDICAL FACILITIES. CONTRACTOR MAY PREPARE THEIR OWN HASP, BUT IT MUST INCLUDE THE INFORMATION PROVIDED IN THE GIVEN HASP AND BE CERTIFIED BY A

2. CONTRACTOR SHALL HOLD A PRE-CONSTRUCTION MEETING THAT INCLUDES A DISCUSSION OF THE SMP AND THE SITE'S HASP AS PART OF THE AGENDA. 3. CONTRACTOR SHALL CONDUCT DAILY TAILGATE MEETINGS THAT INCLUDE A JOB

SAFETY ANALYSIS AND A REVIEW OF THE DUST CONTROL PLAN. 4. CONTRACTOR SHALL CONDUCT A DAILY INSPECTION OF ANY STOCKPILED MATERIAL TO CONFIRM DUST, EROSION, AND STORMWATER CONTROL EFFORTS.

CONTRACTOR SHALL REVIEW THIS DOCUMENT IN ITS ENTIRETY AND SIGN THE SOIL MANAGEMENT PLAN ACKNOWLEDGEMENT FORM, TO BE KEPT ON FILE. 6. CONTRACTOR TO REFER TO THE SOIL MANAGEMENT PLAN (SMP) FOR FURTHER

### **BLUE HERON PARK**

Project Timeline Project Budget

About the Project: The project consists of the removal of arsenic impacted soils. replacement with clean soil, and replacement of the existing walking path.

Mayor Tim Meerbott

Michael P. Callahan Robert "BJ" Duncan Vice-Mayor Councilmember

Suzy Lord Councilmember Richard Ramirez Councilmember

Rafael G. Casals, Town Manager Etienne Bejarano, Project Manager

Project Contractor

An Excellent Place to Live, Work and Play www.cutlerbay-fl.gov

PROJECT SIGN

FOR REFERENCE ONLY. CONTRACTOR TO UPDATE TEXT WITH PROJECT RELATED INFORMATION AS NECESSARY.

THE PRESENCE OF GROUNDWATER SHOULD BE ANTICIPATED. CONTRACTOR'S BID SHALL NCLUDE CONSIDERATION FOR ADDRESSING THIS ISSUE AND OBTAINING ALL NECESSARY PERMITS

ALL ELEVATIONS SHOWN ON THESE PLANS ARI BASED ON THE NGVD 29. TO CONVERT ELEVATIONS TO NAVD 88, SUBTRACT 1.52'.



KNOW WHAT'S BELOV ALWAYS CALL 811 BEFORE YOU DIG

It's fast. It's free. It's the law.


SHEET NUMBER C100.0


ITB No. 25-06 SOIL REMEDIATION PROJECT FOR BLUE HERON PARK Addendum No. 1

Page 8 of 26

0

**((()** 





LEGEND: CENTERLINE RIGHT OF WAY PROPERTY BOUNDARY TREE/PALM PROTECTION ZONE CONTAMINATED SOIL PAVEMENT TO BE REMOVED • EXIST. EXERCISE EQUIPMENT

SF——SF——— PROP. SILT FENCE

CONTRACTOR NOTES:

1. APPROPRIATE EQUIPMENT SHALL BE USED TO MEASURE REAL TIME ATMOSPHERIC CONDITIONS AT THE SITE DURING PERIODS OF DUST GENERATING ACTIVITIES TO SUPPORT THE LOCATIONS OF UPWIND AND DOWNWIND TOTAL DUST MONITORING STATIONS, AS WELL AS INFORM THE ON-SITE CONTRACTOR OF NECESSARY PREVENTATIVE ACTIONS. THE TYPE OF EQUIPMENT USED AND THE TIME/LOCATION OF MEASUREMENTS/READINGS SHALL BE PROVIDED IN EACH QUARTERLY SOIL MANAGEMENT OPERATING REPORT (SMOR). ADDITIONALLY, TOTAL DUST MONITORING READINGS, PRESENTED IN GRAPHICAL FORMAT, SHALL BE PROVIDED IN EACH SMOR.

- CONTRACTOR TO REFER TO THE SOIL MANAGEMENT PLAN (SMP) FOR ADDITIONAL REQUIREMENTS. CONTRACTOR TO PERFORM SITE VISIT PRIOR TO BID SUBMITTAL FOR THE PROJECT. CONTRACTOR TO VERIFY LOCATION OF ALL EXISTING UTILITIES PRIOR TO BEGINNING CONSTRUCTION,
- CONTRACTOR TO NOTIFY ENGINEER OF ANY CONFLICTS. 5. IT SHALL BE THE CONTRACTOR'S SOLE RESPONSIBILITY TO TAKE THE NECESSARY PRECAUTIONS TO
- ENSURE PROPER SAFETY AND WORKMANSHIP WHEN WORKING IN THE VICINITY OF EXISTING UTILITY
- 6. ALL EXISTING UTILITIES, INCLUDING BUT NOT LIMITED TO, DRAINAGE CLEANOUTS, WATER METERS, ELECTRICAL METERS, AND IRRIGATION MAINS, IMPACTED BY SIDEWALK CONSTRUCTION SHALL BE MODIFIED/RELOCATED AS NECESSARY. CONTRACTOR TO COORDINATE WITH UTILITY COMPANY DIRECTLY. ELEVATION OF EXISTING UTILITIES SHALL BE ADJUSTED AS NECESSARY. 7. THE INTENT OF THE DEMOLITION PLAN IS TO DEPICT ALL EXISTING FEATURES THAT ENCUMBER THE
- PROPOSED CONSTRUCTION AREA AND ARE SCHEDULED FOR REMOVAL. SOME INCIDENTAL ITEMS MAY HAVE BEEN INADVERTENTLY OMITTED FROM THE PLAN. THE CONTRACTOR IS ENCOURAGED TO THOROUGHLY INSPECT THE SITE AS WELL AS REVIEW THE PLANS PRIOR TO SUBMITTING PRICING. CONTRACTOR WILL NOT RECEIVE ADDITIONAL COMPENSATION FOR INCIDENTAL ITEMS NOT SHOWN ON THIS DEMOLITION PLAN. ANY EXISTING ON-SITE HARDSCAPE FEATURES, INCLUDING BUT NOT LIMITED TO WASTE RECEPTACLES, SIGNAGE, EXERCISE EQUIPMENT, BENCHES, ETC., INADVERTENTLY OMITTED FROM THE SURVEY ARE TO BE REMOVED AND REPLACED IN THEIR EXISTING LOCATIONS.
- 8. REFER TO THE TREE DISPOSITION PLAN FOR TREE REMOVAL, ROOT PRUNING, TRIMMING, AND TREE PROTECTION LOCATIONS.
- 9. ALL AREAS DAMAGED BY THE CONTRACTOR, INCLUDING BUT NOT LIMITED TO PAVEMENT MARKINGS, ASPHALT, SWALE, SIDEWALK, AND DRIVEWAYS, SHALL BE RESTORED, AT THE CONTRACTOR'S EXPENSE, TO ORIGINAL CONDITION.
- 10. SAWCUTTING OF THE EXISTING SIDEWALK SHALL BE MADE ONLY AT THE NEAREST FLAG JOINT. 11. SHOULD TREE REMOVAL/RELOCATION BE REQUIRED, CONTRACTOR TO OBTAIN ALL REQUIRED PERMITS.
  12. CONTRACTOR TO OBTAIN ENGINEERING PERMIT.

THE PRESENCE OF GROUNDWATER SHOULD BE ANTICIPATED. CONTRACTOR'S BID SHALL INCLUDE CONSIDERATION FOR ADDRESSING THIS ISSUE AND OBTAINING ALL NECESSARY PERMITS

ALL ELEVATIONS SHOWN ON THESE PLANS . BASED ON THE NGVD 29. TO CONVERT ELEVATIONS TO NAVD 88, SUBTRACT 1.52'.




KNOW WHAT'S BELOW ALWAYS CALL 811 BEFORE YOU DIG It's fast. It's free. It's the law.

ITB No. 25-06 SOIL REMEDIATION PROJECT FOR BLUE HERON PARK Addendum No. 1 Page 9 of 26

OF


DEMOLIT

SHEET NUMBER C200.0




SHEET NUMBER C200.1

Page 10 of 26



AND

SHEET NUMBER C200.2



DEMOLIT

OF

SHEET NUMBER C200.3

THIS PLAN HAS BEEN PREPARED TO ENSURE COMPLIANCE WITH APPROPRIATE CONDITIONS OF THE BROWARD COUNTY LAND DEVELOPMENT REGULATIONS, THE RULES OF THE FLORIDA DEPARTMENT OF ENVIRONMENTAL PROTECTION (FDEP), CHAPTER 17-25, F.A.C., THE SOUTH FLORIDA WATER MANAGEMENT DISTRICT (SFWMD), CHAPTER 40D-4, F.A.C. AND THE UNITED STATES ENVIRONMENTAL PROTECTION AGENCY (ÉPA) DOCUMENT NO. EPA 832/R-92-005 (SEPTEMBER 1992). THE PLAN ADDRESSES THE FOLLOWING:

- A. PREVENT LOSS OF SOIL DURING CONSTRUCTION BY STORMWATER RUNOFF AND/OR WIND EROSION, INCLUDING PROTECTING TOPSOIL BY STOCKPILING FOR REUSE.
- B. SEDIMENTION PROTECTION OF STORM SEWER OR RECEIVING STREAM.
- C. PREVENT POLLUTING THE AIR WITH DUST AND PARTICULATE MATTER. THE VARIOUS TECHNIQUES OR ACTIONS IDENTIFIED UNDER EACH SECTION INDICATE THE APPROPRIATE SITUATION WHEN THE TECHNIQUES SHOULD BE EMPLOYED. ALSO IDENTIFIED IS A CROSS-REFERENCE TO A DIAGRAM OR FIGURE REPRESENTING THE TECHNIQUE. IT SHOULD BE NOTED THAT THE MEASURES IDENTIFIED ON THIS PLAN ARE ONLY SUGGESTED BMP(S). THE CONTRACTOR SHALL PROVIDE POLLUTION PREVENTION AND EROSION CONTROL MEASURES AS SPECIFIED IN ACCORDANCE WITH THE CURRENT FLORIDA DEPARTMENT OF ENVIRONMENTAL PROTECTION NATIONAL POLLUTION DISCHARGE ELIMINATION SYSTEM (NPDES) REQUIREMENTS. CONTRACTOR SHALL PREPARE REQUIRED NPDES DOCUMENTATION AND OBTAIN PERMIT PRIOR TO COMMENCEMENT OF CONSTRUCTION. IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO PREPARE THE REQUIRED NPDES DOCUMENT AND OBTAIN THE NPDES PERMIT. ALL COST ASSOCIATED WITH SUCH WORK SHALL BE DEEMED INCIDENTAL TO THE PROJECT LUMP SUM COST.

### **GENERAL EROSION CONTROL NOTES:**

- A. THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IS COMPRISED OF THESE EROSION CONTROL DRAWINGS, THE STANDARD DETAILS, THE NPDES PERMIT (TO BE OBTAINED BY CONTRACTOR) AND ALL SUBSEQUENT REPORTS AND RELATED
- B. ALL CONTRACTORS AND SUBCONTRACTORS INVOLVED WITH STORM WATER POLLUTION PREVENTION SHALL OBTAIN A COPY OF THIS DRAWING AND THE STATE OF FLORIDA NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM GENERAL PERMIT (NPDES PERMIT) AND BECOME FAMILIAR WITH THEIR CONTENTS
- C. CONTRACTOR SHALL IMPLEMENT BEST MANAGEMENT PRACTICES (BMP) IN ALL CONSTRUCTION ACTIVITIES INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
- FUEL SPILLS AND LEAKS PREVENTION
- PREVENT/REDUCE VEHICLE AND EQUIPTMENT WASHING AND STEAM CLEANING VEHICLE AND EQUIPTMENT MAINTENANCE AND REPAIR
- PROPER OUTDOOR LOADING/UNLOADING OF MATERIALS PREVENT/REDUCE OUTDOOR STORAGE OF RAW MATERIALS, PRODUCTS, AND
- **BY-PRODUCTS** SOLID WASTE MANAGEMENT

CONSTRUCTION.

- HAZARDOUS WASTE MANAGEMENT CONCRETE WASTE MANAGEMENT
- SANDBLASTING WASTE MANAGEMEN STRUCTURE CONSTRUCTION AND PAINTING
- SPILL PREVENTION AND CONTROL CONTAMINATED SOIL MANAGEMENT
- SANITARY/SEPTIC WASTE MANAGEMENT
- SOIL EROSION CONTROL STORM WATER TURBIDITY MANAGEMENT

ADDITIONAL BEST MANAGEMENT PRACTICES SHALL BE IMPLEMENTED AS DICTATED BY CONDITIONS AT NO ADDITIONAL COST TO THE OWNER THROUGHOUT ALL PHASES OF

- D. BEST MANAGEMENT PRACTICES (BMPS) AND CONTROLS SHALL CONFORM TO FEDERAL, STATE, OR LOCAL REQUIREMENTS OR MANUAL OF PRACTICE, AS APPLICABLE. CONTRACTOR SHALL IMPLEMENT ADDITIONAL CONTROLS AS DIRECTED BY PERMITTING AGENCY OR OWNER.
- E. SITE MAP MUST CLEARLY DELINEATE ALL STATE WATERS. CONTRACTOR MUST MAINTAIN ALL PERMITS FOR ANY CONSTRUCTION ACTIVITY IMPACTING STATE WATERS OR REGULATED WETLANDS ON SITE AT ALL TIMES
- F. CONTRACTOR SHALL MINIMIZE CLEARING TO THE MAXIMUM EXTENT PRACTICAL OR AS REQUIRED BY THE GENERAL PERMIT.
- G. CONTRACTOR SHALL BEGIN CLEARING AND GRUBBING THOSE PORTIONS OF THE SITE NECESSARY TO IMPLEMENT PERIMETER CONTROL MEASURES. CLEARING AND GRUBBING FOR THE REMAINING PORTIONS OF THE PROPOSED SITE SHALL COMMENCE ONCE PERIMETER CONTROLS ARE IN PLACE, PERIMETER CONTROLS SHALL BE ACTIVELY MAINTAINED UNTIL SAID AREAS HAVE BEEN STABILIZED AND SHALL BE REMOVED ONCE FINAL STABILIZATION IS COMPLETE.
- H. GENERAL EROSION CONTROL BMPS SHALL BE EMPLOYED TO MINIMIZE SOIL EROSION AND POTENTIAL LAKE SLOPE CAVE-INS. WHILE THE VARIOUS TECHNIQUES REQUIRED WILL BE SITE AND PLAN SPECIFIC, THEY SHOULD BE EMPLOYED AS SOON AS POSSIBLE DURING CONSTRUCTION.
- I. ON-SITE & OFF-SITE SOIL STOCKPILE AND BORROW AREAS SHALL BE PROTECTED FROM EROSION AND SEDIMENTATION THROUGH IMPLEMENTATION OF BEST MANAGEMENT PRACTICES. STOCKPILE AND BORROW AREA LOCATIONS SHALL BE NOTED ON THE SITE MAP AND PERMITTED IN ACCORDANCE WITH GENERAL PERMIT REQUIREMENTS.
- J. SURFACE WATER QUALITY SHALL BE MAINTAINED BY EMPLOYING THE FOLLOWING BMP'S IN THE CONSTRUCTION PLANNING AND CONSTRUCTION OF ALL IMPROVEMENTS.

## STORM WATER EROSION CONTROL

A. CONTRACTORS OR SUBCONTRACTORS WILL BE RESPONSIBLE FOR REMOVING SEDIMENT FROM DETENTION PONDS AND ANY SEDIMENT THAT MAY HAVE COLLECTED IN THE STORM SEWER DRAINAGE SYSTEMS IN CONJUNCTION WITH THE STABILIZATION OF THE SITE.

B. SLOPES SHALL BE LEFT IN A ROUGHENED CONDITION DURING THE GRADING PHASE TO REDUCE RUNOFF VELOCITIES AND EROSION.

C. DUE TO THE GRADE CHANGES DURING THE DEVELOPMENT OF THE PROJECT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ADJUSTING THE EROSION CONTROL MEASURES (COMPOST SOCK DEVICES, ETC.) TO PREVENT EROSION.

- D. WHERE PRACTICAL, STORMWATER SHALL BE CONVEYED BY SWALES.
- E. EROSION CONTROL MEASURES SHALL BE EMPLOYED TO MINIMIZE TURBIDITY OF SURFACE WATERS LOCATED DOWNSTREAM OF ANY CONSTRUCTION ACTIVITY. WHILE THE VARIOUS MEASURES REQUIRED WILL BE SITE SPECIFIC, THEY SHALL BE EMPLOYED AS NEEDED IN ACCORDANCE WITH THE FOLLOWING:
- IN GENERAL, EROSION SHALL BE CONTROLLED AT THE FURTHEST PRACTICAL UPSTREAM LOCATION.
- STORMWATER INLETS SHALL BE PROTECTED DURING CONSTRUCTION. PROTECTION MEASURES SHALL BE EMPLOYED AS SOON AS PRACTICAL DURING THE VARIOUS STAGES OF INLET CONSTRUCTION. SILT BARRIERS SHALL REMAIN IN PLACE UNTIL SODDING AROUND INLETS IS COMPLETE.
- WHEN NEEDED A TEMPORARY SEDIMENT TRAP SHOLD BE CONSTRUCTED TO DETAIN SEDIMENT-LADEN RUNOFF FROM DISTURBED AREAS.
- F. SILT BARRIERS, ANY SILT WHICH ACCUMULATES BEHIND THE BARRIERS, AND ANY FILL USED TO ANCHOR THE BARRIERS SHALL BE REMOVED PROMPTLY AFTER THE END OF THE MAINTENANCE PERIOD SPECIFIED FOR THE BARRIERS.

1. CONTRACTOR TO CONSIDER POTENTIAL DEWATERING ACTIVITIES WHEN PREPARING BID DOCUMENTS FOR THIS PROJECT.

STORMWATER DISCHARGE FROM CONSTRUCTION ACTIVITIES AND DEWATERING OPERATIONS.

GROUNDWATER SOIL TREATMENT.

2. CONTRACTOR SHALL OBTAIN ANY NECESSARY DEWATERING PERMITS AS SITE CONDITIONS AND CONSTRUCTION ACTIVITIES REQUIRE.

3. CONTRACTOR TO USE BEST MANAGEMENT PRACTICES TO ENSURE COMPLIANCE WITH NPDES AND WATER MANAGEMENT DISTRICT REGULATIONS FOR

4. IT SHOULD BE NOTED THAT THE MEASURE IDENTIFIED ON THIS PLAN ARE ONLY SUGGESTED BMP(S). THE CONTRACTOR SHALL PROVIDE POLLUTION

5. SITE PREPARATION SHOULD BE IN ACCORDANCE WITH GEOTECHNICAL INVESTIGATION WHICH DISCUSSES SPECIFIC RECOMMENDATIONS REGARDING

PREVENTION AND EROSION CONTROL MEASURES AS NECESSARY TO CONFORM TO CURRENT CITY, FDEP AND SFWMD CODES AND SPECIFICATIONS.

- G. SLOPES OF BANKS OF RETENTION/DETENTION PONDS SHALL BE CONSTRUCTED NOT STEEPER THAN 3H:1V FROM TOP OF BANK TO TWO FEET BELOW NORMAL WATER LEVEL, AS
- H. SOD SHALL BE PLACED FOR A 2-FOOT WIDE STRIP ADJOINING ALL CURBING AND AROUND ALL INLETS. SOD SHALL BE PLACED BEFORE SILT BARRIERS ARE REMOVED.
- I. WHERE REQUIRED TO PREVENT EROSION FROM SHEET FLOW ACROSS BARE GROUND FROM ENTERING A LAKE OR SWALE, A TEMPORARY SEDIMENT SUMP SHALL BE CONSTRUCTED.
- J. FILTER FABRIC SHOULD BE USED FOR STORM DRAIN INLET PROTECTION BEFORE FINAL

### WIND EROSION CONTROL PRACTICES

- A. WIND EROSION SHALL BE CONTROLLED BY EMPLOYING THE FOLLOWING METHODS AS **NECESSARY AND APPROPRIATE**
- BARE EARTH AREAS SHALL BE WATERED DURING CONSTRUCTION AS NECESSARY TO MINIMIZE THE TRANSPORT OF FUGITIVE DUST. IT MAY BE NECESSARY TO LIMIT CONSTRUCTION VEHICLE SPEED IF BARE EARTH HAS NOT BEEN EFFECTIVELY WATERED. IN NO CASE SHALL FUGITIVE DUST BE ALLOWED TO LEAVE THE SITE UNDER CONSTRUCTION
- DISTURBED PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITY HAS PERMANENTLY STOPPED SHALL BE PERMANENTLY SEEDED (SEE PERMANENT STABALIZATION PRACTICES FOR DETAILS). THESE AREAS SHALL BE SEEDED NO LATER THAN 14 DAYS AFTER THE LAST CONSTRUCTION ACTIVITY OCCURRING IN THESE AREAS. REFER TO THE GRADING PLAN AND/OR LANDSCAPE PLAN. CLEARED SITE DEVELOPMENT AREAS NOT CONTINUALLY SCHEDULED FOR CONSTRUCTION ACTIVITIES SHALL BE COVERED WITH HAY OR OVERSEEDED AND PERIODICALLY WATERED SUFFICIENTLY TO STABILIZE THE TEMPORARY GROUNDCOVER (SEE TEMPORARY STABALIZATION PRACTICES FOR DETAILS)
- AT ANY TIME BOTH DURING AND AFTER SITE CONSTRUCTION THAT WATERING AND/OR VEGETATION ARE NOT EFFECTIVE IN CONTROLLING WIND EROSION AND/OR TRANSPORT OF FUGITIVE DUST, OTHER METHODS AS ARE NECESSARY FOR SUCH CONTROL SHALL BE EMPLOYED. THESE METHODS SHOULD INCLUDE ERECTION OF DUST CONTROL FENCES. A 6-FT GEOTEXTILE FILTER FIBER SHOULD BE HANGING AGAINST THE EXISTING TEMPORARY CONSTRUCTION FENCE AND GATE.
- B. ALL DUST ON THE SITE SHALL BE CONTROLLED. THE USE OF MOTOR OILS AND OTHER PETROLEUM BASED OR TOXIC LIQUIDS FOR DUST SUPPRESSION OPERATIONS IS

### STABILIZATION PRACTICES

SHALL BE IN ACCORDANCE WITH DEP DOCUMENT NO 62-621.300(4)(a)

### STRUCTURAL PRACTICES:

SHALL BE IN ACCORDANCE WITH DEP DOCUMENT NO 62-621.300(4)(a)

### WASTE DISPOSAL

- A. WASTE MATERIALS ALL WASTE MATERIALS SHALL BE COLLECTED AND STORED IN A METAL DUMPSTER WITH A SECURE LID IN ACCORDANCE WITH ALL LOCAL AND STATE LAWS. ALL TRASH AND CONSTRUCTION DEBRIS FROM THE SITE SHALL BE DEPOSITED IN THE DUMPSTER. THE SUPERINTENDENT SHALL COORDINATE WITH THE LOCAL UTILITIES TO HAVE THE DUMPSTER EMPTIED AT LEAST TWICE A WEEK AND THE WASTE TAKEN TO AN APPROPRIATE LANDFILL. NO CONSTRUCTION WASTE MATERIALS SHALL BE BURIED ON SITE. THE SUPERINTENDENT SHALL ORGANIZE TRAINING FOR THE EMPLOYEES IN THE PROPER PRACTICES WHEN DEALING WITH WASTE MATERIALS. THE SUPERINTENDENT SHALL BE RESPONSIBLE FOR POSTING AND ENFORCING WASTE MATERIAL PROCEDURES.
- HAZARDOUS WASTE HAZARDOUS WASTE MATERIALS SHALL BE DISPOSED OF IN ACCORDANCE WITH ALL LOCAL AND STATE LAWS OR AS DIRECTED BY THE MANUFACTURER. THE SUPERINTENDENT SHALL ORGANIZE THE PROPER TRAINING FOR EMPLOYEES IN THE PROPER PRACTICES WHEN DEALING WITH HAZARDOUS WASTE MATERIALS. THESE PROCEDURES SHALL BE POSTED ON THE SITE. THE PERSON WHO MANAGES THE SITE SHALL BE RESPONSIBLE FOR ENFORCING THE PROCEDURES
- SANITARY WASTE SANITARY WASTE SHALL BE COLLECTED AND DISPOSED OF IN ACCORDANCE WITH ALL LOCAL AND STATE LAWS. THE SUPERINTENDENT SHALL COORDINATE WITH THE LOCAL UTILITY FOR COLLECTION OF THE SANITARY WASTE AT LEAST THREE TIMES A WEEK TO PREVENT SPILLAGE ONTO THE SITE.
- RUBBISH, TRASH, GARBAGE, LITTER, OR OTHER SUCH MATERIALS SHALL BE DEPOSITED INTO SEALED CONTAINERS. MATERIALS SHALL BE PREVENTED FROM LEAVING THE PREMISES THROUGH THE ACTION OF WIND OR STORM WATER DISCHARGE INTO DRAINAGE DITCHES OR WATERS OF THE STATE.

- A. STABILIZED CONSTRUCTION ENTRANCE SHALL BE PROVIDED TO REDUCE SEDIMENT TRACKING OFFSITE. THE MAJOR ROAD CONNECTED TO THE PROJECT SHALL BE CLEANED ONCE A DAY TO REMOVE ANY EXCESS MUD, DIRT OR ROCK RESULTING FROM CONSTRUCTION TRAFFIC. ALL TRUCKS HAULING MATERIALS OFFSITE SHALL BE COVERED WITH A TARPAULIN.
- GENERAL CONTRACTOR SHALL DENOTE ON PLAN THE TEMPORARY PARKING AND STORAGE AREA WHICH SHALL ALSO BE USED AS THE EQUIPMENT MAINTENANCE AND CLEANING AREA. EMPLOYEE PARKING AREA. AND AREA FOR LOCATION PORTABLE FACILITIES, OFFICE TRAILERS, AND TOILET FACILITIES. HEAVY CONSTRUCTION EQUIPMENT PARKING AND MAINTENANCE AREAS SHALL BE DESIGNED TO PREVENT OIL, GREASE, AND LUBRICANTS FROM ENTERING SITE DRAINAGE FEATURES INCLUDING STORMWATER COLLECTION AND TREATMENT SYSTEMS. CONTRACTORS SHALL PROVIDE BROAD DIKES, HAY BALES OR SILT SCREENS AROUND, AND SEDIMENT SUMPS WITHIN, SUCH AREAS AS REQUIRED TO CONTAIN SPILLS OF OIL, GREASE OR LUBRICANTS. CONTRACTORS SHALL HAVE AVAILABLE, AND SHALL USE, ABSORBENT FILTER PADS TO CLEAN UP SPILLS AS SOON AS POSSIBLE AFTER OCCURRENCE.
- C. ALL WASH WATER FROM CONCRETE TRUCKS, VEHICLE CLEANING, EQUIPMENT CLEANING,
- ETC. SHALL BE DETAINED ON SITE AND SHALL BE PROPERLY TREATED OR DISPOSED. D. IF THE ACTION OF VEHICLES TRAVELING OVER THE GRAVEL CONSTRUCTION ENTRANCES IS NOT SUFFICIENT TO REMOVE THE MAJORITY OF DIRT OR MUD, THEN THE TIRES MUST BE WASHED BEFORE THE VEHICLES ENTER A PUBLIC ROAD. IF WASHING IS USED. PROVISIONS MUST BE MADE TO INTERCEPT THE WASH WATER AND TRAP THE SEDIMENT BEFORE IT IS CARRIED OFF THE SITE.
- E. ALL MATERIALS SPILLED, DROPPED, WASHED, OR TRACKED FROM VEHICLES ONTO ROADWAYS OR INTO STORM DRAINS MUST BE REMOVED IMMEDIATELY.

### **MAINTENANCE:**

ALL MEASURES STATED ON THIS EROSION AND SEDIMENT CONTROL PLAN, AND IN THE STORM WATER POLLUTION PREVENTION PLAN, SHALL BE MAINTAINED IN FULLY FUNCTIONAL CONDITION UNTIL NO LONGER REQUIRED FOR A COMPLETED PHASE OF WORK OR FINAL STABILIZATION OF THE SITE. ALL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE CHECKED BY A QUALIFIED PERSON AT LEAST ONCE EVERY SEVEN CALENDAR DAYS AND WITHIN 24 HOURS OF THE END OF A 0.5" RAINFALL EVENT, AND CLEANED AND REPAIRED IN ACCORDANCE WITH THE FOLLOWING:

- A. INLET PROTECTION DEVICES AND BARRIERS SHALL BE REPAIRED OR REPLACED IF THEY SHOW SIGNS OF UNDERMINING, OR DETERIORATION.
- B. B. ALL SEEDED AREAS SHALL BE CHECKED REGULARLY TO SEE THAT A GOOD STAND IS MAINTAINED. AREAS SHOULD BE FERTILIZED, WATERED, AND RESEEDED AS NEEDED.

- C. THE COMPOST ROCK FILTRATION DEVICE SHALL BE INSPECTED PERIODICALLY FOR HEIGHT OF SEDIMENT AND CONDITION OF DEVICE. COMPOST SOCK SHALL BE REPAIRED TO ITS ORIGINAL CONDITIONS IF DAMAGED. SEDIMENT SHALL BE REMOVED FROM THE COMPOST SOCK WHEN IT REACHES ONE-THIRD THE HEIGHT OF THE COMPOST SOCK
- D. THE CONSTRUCTION ENTRANCES SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF MUD ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING OF THE CONSTRUCTION ENTRANCES AS CONDITIONS DEMAND.
- E. THE TEMPORARY PARKING AND STORAGE AREA SHALL BE KEPT IN GOOD CONDITION (SUITABLE FOR PARKING AND STORAGE). THIS MAY REQUIRE PERIODIC TOP DRESSING OF THE TEMPORARY PARKING AS CONDITIONS DEMAND.
- F. OUTLET STRUCTURES IN THE SEDIMENTATION BASINS SHALL BE MAINTAINED IN OPERATIONAL CONDITIONS AT ALL TIMES. THE SEDIMENT BASINS/DITCHES SHALL BE CHECKED MONTHLY FOR DEPTH OF SEDIMENT. SEDIMENT SHALL BE REMOVED FROM SEDIMENT BASINS OR TRAPS WHEN THE DESIGN CAPACITY HAS BEEN REDUCED BY 10% AND AFTER CONSTRUCTION IS COMPLETE
- G. ALL MAINTENANCE OPERATIONS SHALL BE DONE IN A TIMELY MANNER BUT IN NO CASE LATER THAN SEVEN CALENDAR DAYS FOLLOWING THE INSPECTION.DIVERSION DIKES SHALL BE INSPECTED MONTHLY. ANY BREACHES SHALL BE PROMPTLY REPAIRED.
- H. A MAINTENANCE REPORT SHALL BE COMPLETED DAILY AFTER EACH INSPECTION OF THE SEDIMENT AND EROSION CONTROL METHODS. THE REPORTS SHALL BE FILED IN AN ORGANIZED MANNER AND RETAINED ON-SITE DURING CONSTRUCTION. AFTER CONSTRUCTION IS COMPLETED, THE REPORTS SHALL BE SAVED FOR AT LEAST THREE YEARS. THE REPORTS SHALL BE AVAILABLE FOR ANY AGENCY THAT HAS JURISDICTION OVER EROSION CONTROL.
- I. ALL REPAIRS MUST BE MADE WITHIN 24 HOURS OF REPORT.
- J. THE SUPERINTENDENT SHALL ORGANIZE THE TRAINING FOR INSPECTION PROCEDURES AND PROPER EROSION CONTROL METHODS FOR EMPLOYEES THAT COMPLETE INSPECTIONS AND REPORTS.
- K. SILT FENCES SHALL BE REPAIRED TO THEIR ORIGINAL CONDITIONS IF DAMAGED. SEDIMENT SHALL BE REMOVED FROM THE SILT FENCES WHEN IT REACHES ONE-HALF THE HEIGHT OF

### SPILL PREVENTION AND CONTROL:

THE FOLLOWING ARE THE MATERIAL MANAGEMENT PRACTICES THAT WILL BE USED TO REDUCE THE RISK OF SPILLS OR OTHER ACCIDENTAL EXPOSURE OF MATERIALS AND SUBSTANCES TO STORM WATER RUNOFF

### A. GOOD HOUSEKEEPING

- 1. SUPERINTENDENT SHALL INSPECT PROJECT AREA DAILY FOR PROPER STORAGE, USE, AND DISPOSAL OF CONSTRUCTION MATERIALS
- 2. STORE ONLY ENOUGH MATERIAL ON SITE FOR PROJECT COMPLETION.
- 3. ALL SUBSTANCES SHOULD BE USED BEFORE DISPOSAL OF CONTAINER.
- 4. ALL CONSTRUCTION MATERIALS STORED SHALL BE ORGANIZED AND IN THE PROPER CONTAINER AND IF POSSIBLE, STORED UNDER A ROOF OR PROTECTIVE COVER.
- 5. PRODUCTS SHALL NOT BE MIXED UNLESS DIRECTED BY THE MANUFACTURER
- 6. ALL PRODUCTS SHALL BE USED AND DISPOSED OF ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS.

### B. HAZARDOUS PRODUCTS

- 1. MATERIALS SHOULD BE KEPT IN ORIGINAL CONTAINER WITH LABELS UNLESS THE ORIGINAL CONTAINERS CANNOT BE RESEALED. IF ORIGINAL CONTAINERS CANNOT BE USED, LABELS AND PRODUCT INFORMATION SHALL BE SAVED.
- 2. PROPER DISPOSAL PRACTICES SHALL ALWAYS BE FOLLOWED IN ACCORDANCE WITH MANUFACTURER AND LOCAL/STATE REGULATIONS.

C. PRODUCT SPECIFIC PRACTICES

- 1. PETROLEUM PRODUCTS MUST BE STORED IN PROPER CONTAINERS AND CLEARLY LABELED. VEHICLES CONTAINING PETROLEUM PRODUCTS SHALL BE PERIODICALLY INSPECTED FOR LEAKS. PRECAUTIONS SHALL BE TAKEN TO AVOID LEAKAGE OF PETROLEUM PRODUCTS ON SITE.
- 2. THE MINIMUM AMOUNT OF FERTILIZER SHALL BE USED AND MIXED INTO THE SOIL IN ORDER TO LIMIT EXPOSURE TO STORM WATER. FERTILIZERS SHALL BE STORED IN A COVERED SHED. THE CONTENTS OF ANY PARTIALLY USED BAGS OF FERTILIZER SHALL BE TRANSFERRED TO A SEALABLE PLASTIC BIN TO AVOID SPILLS.
- 3. PAINT CONTAINERS SHALL BE SEALED AND STORED WHEN NOT IN USE, EXCESS PAINT MUST BE DISPOSED OF IN AN APPROVED MANNER
- 4. CONCRETE TRUCKS SHALL NOT BE ALLOWED TO WASH OUT OR DISCHARGE SURPLUS CONCRETE OR DRUM WASH WATER ON THE SITE.

### SPILL CLEAN UP:

IN ADDITION TO THE GOOD HOUSEKEEPING AND MATERIAL MANAGEMENT PRACTICES DISCUSSED ABOVE, THE FOLLOWING PRACTICES SHALL BE FOLLOWED FOR SPILL PREVENTION AND CLEANUP:

- A. SPILL CLEANUP INFORMATION SHALL BE POSTED ON SITE TO INFORM EMPLOYEES ABOUT CLEANUP PROCEDURES AND RESOURCES
- STORAGE AREA: GLOVES, MOPS, RAGS, BROOMS, DUST PANS, SAND, SAWDUST, LIQUID ABSORBER, GOGGLES, AND TRASH CONTAINERS. C. SUFFICIENT OIL AND GREASE ABSORBING MATERIALS AND FLOTATION BOOMS SHALL BE

B. THE FOLLOWING CLEAN-UP EQUIPMENT MUST BE KEPT ON-SITE NEAR THE MATERIAL

- MAINTAINED ONSITE AND READILY AVAILABLE TO CONTAIN AND CLEAN-UP FUEL OR CHEMICAL SPILLS AND LEAKS.
- D. ALL SPILLS SHALL BE CLEANED UP AS SOON AS POSSIBLE.
- E. WHEN CLEANING A SPILL, THE AREA SHOULD BE WELL VENTILATED AND THE EMPLOYEE SHALL WEAR PROPER PROTECTIVE COVERING TO PREVENT INJURY.
- F. TOXIC SPILLS MUST BE REPORTED TO THE PROPER AUTHORITY REGARDLESS OF THE SIZE OF THE SPILL. G. AFTER A SPILL, THE PREVENTION PLAN SHALL BE REVIEWED AND CHANGED TO PREVENT FURTHER SIMILAR SPILLS FROM OCCURRING. THE CAUSE OF THE SPILL, MEASURES TO
- H. THE SUPERINTENDENT SHALL BE THE SPILL PREVENTION AND CLEANUP COORDINATOR AND IS RESPONSIBLE FOR THE DAY TO DAY SITE OPERATIONS. THE SUPERINTENDENT ALSO OVERSEES THE SPILL PREVENTION PLAN AND SHALL BE RESPONSIBLE FOR EDUCATING THE EMPLOYEES ABOUT SPILL PREVENTION AND CLEANUP PROCEDURES.

### SEQUENCE OF CONSTRUCTION

CHECK DAMS, OUTLET TRAPS, ETC.)

ONSITE DRAINAGE SYSTEM HAS BEEN INSTALLED.

PREVENT IT, AND HOW TO CLEAN THE SPILL UP SHALL BE RECORDED.


UPON IMPLEMENTATION AND INSTALLATION OF THE FOLLOWING AREAS: TRAILER, PARKING, LAY DOWN, PORTA-POTTY, WHEEL WASH, CONCRETE WASHOUT, FUEL AND MATERIAL STORAGE CONTAINERS, SOLID WASTE CONTAINERS, ETC., IMMEDIATELY DENOTE THEM ON THE SITE MAPS AND NOTE ANY CHANGES IN LOCATION AS THEY OCCUR THROUGHOUT THE CONSTRUCTION PROCESS.

- CONSTRUCT STABILIZED CONSTRUCTION ENTRANCE AND INSTALL SILT FENCE DEMOLISH EXISTING STRUCTURES (IF APPLICABLE)
- CONSTRUCT AND STABILIZE SEDIMENT BASIN AND DRAINAGE SWALES WITH APPROPRIATE OUTFALL STRUCTURES (CLEAR ONLY THOSE AREAS NECESSARY TO INSTALL CONTROL DEVICES LISTED ABOVE)
- PREPARE CLEARING AND GRUBBING OF THE SITE, (IF APPLICABLE) START CONSTRUCTION OF THE BUILDING PAD AND STRUCTURES
- PERFORM MASS GRADING, ROUGH GRADE TO ESTABLISH PROPOSED DRAINAGE 8. TEMPORARILY SEED, THROUGHOUT CONSTRUCTION, DISTURBED AREAS THAT WILL BE INACTIVE FOR 7 DAYS OR MORE AS REQUIRED BY GENERIC PERMIT OFFSITE HEADWALL CONNECTION TO OPWCD SHALL BE MADE AFTER THE ENTIRE

INSTALL AND STABILIZE ANY NECESSARY HYDRAULIC CONTROL STRUCTURES (DIKES,


HALT ALL ACTIVITIES AND CONTACT THE CIVIL ENGINEER CONSULTANT TO PERFORM INSPECTION AND CERTIFICATION OF BMPS. GENERAL CONTRACTOR SHALL SCHEDULE AND CONDUCT STORM WATER PRE-CONSTRUCTION MEETING WITH ENGINEER AND ALL GROUND DISTURBING CONTRACTORS BEFORE PROCEEDING WITH CONSTRUCTION.

CONTRACTOR TO BE RESPONSIBLE FOR OBTAINING ALL DEWATERING PERMITS NECESSARY




THE METHOD SHALL NOT APPLY TO INLETS RECEIVING CONCENTRATED FLOWS, THE GROUND ELEVATION DOWNSLOPE TO PREVENT RUNOFF FROM BY SUCH AS IN STREET OR HIGHWAY MEDIANS. PASSING THE INLET. A TEMPORARY DIKE MAY BE NECESSARY ON


FILTER FABRIC DROP INLET SEDIMENT BARRIEF



THE TOP OF THE FRAME (PONDING HEIGHT) MUST BE WELL BELOW

THE DOWNSLOPE SIDE OF THE STRUCTURE.






TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE TOP DRESSING, REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT.

WHEN NECESSARY, WHEELS SHALL BE CLEANED PRIOR TO ENTRANCE ONTO

PUBLIC RIGHT-OF-WAY.

WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP OR SEDIMENT BASIN. TEMPORARY GRAVEL CONSTRUCTION ENTRANCE




FILTER FABRIC

MATERIAL

IS A RELATIVELY FLAT AREA (SLOPE NO GREATER THAN 5%) WHERE THE

SPACING OF

INLET SHEET OR OVERLAND FLOWS (NOT EXCEEDING 1 C.F.S.) ARE TYPICAL.



- CONTRACTOR SHALL PERFORM DAILY INSPECTIONS OF GEO-TEXTILE FABRIC BARRIER AND AS NECESSARY REPLACE OR REPAIR AS REQUIRED. SPECIFICALLY AFTER STORM EVENTS AND LARGE
- RAINFALL EVENTS. SEDIMENTATION AND DEBRIS THAT ARE REMOVED FROM BARRIERS SHALL BE LEGALLY DISPOSED OF AT AN AUTHORIZED OFF-SITE DISPOSAL FACILITY.

DROP INLET SEDIMENT NOT TO SCALE

THE PRESENCE OF GROUNDWATER SHOULD BE ANTICIPATED. CONTRACTOR'S BID SHALL NCLUDE CONSIDERATION FOR ADDRESSING THIS SSUE AND OBTAINING ALL NECESSARY PERMITS

ALL ELEVATIONS SHOWN ON THESE PLANS . BASED ON THE NGVD 29. TO CONVERT ELEVATIONS TO NAVD 88, SUBTRACT 1.52'.




KNOW WHAT'S BELO' **ALWAYS CALL 811 BEFORE YOU DIG** lt's fast. It's free. It's the law.

SHEET NUMBER C201.0

ITB No. 25-06 SOIL REMEDIATION PROJECT FOR BLUE HERON PARK Addendum No. 1

Page 13 of 26



LEGEND:

	CENTERLINE
	RIGHT OF WAY
	PROPERTY BOUNDARY
	TREE/PALM PROTECTION ZONE
+ + + + + + + + + + + + + + + + + + + +	PROP. CLEAN SOIL, TOPSOIL, AND ST. AUGUSTINE SOD
A A A A	PROP. CONCRETE
	PROP. FLEXI—PAVE PATH
•	EXIST. EXERCISE EQUIPMENT
	PROP. ROOT BARRIER

CONTRACTOR NOTES:

1. PROPOSED SIDEWALK SLOPE SHALL NOT EXCEED MAXIMUM CROSS SLOPE OF 2% AND LONGITUDINAL SLOPE OF

- 5%. IN NO CASE SHALL AN ACCESSIBLE RAMP SLOPE EXCEED 1 VERTICAL TO 12 HORIZONTAL.

  2. CONTRACTOR TO MAINTAIN DRAINAGE FLOW DURING AND AFTER CONSTRUCTION. CONTRACTOR SHALL ENSURE POSITIVE DRAINAGE AWAY FROM BUILDINGS FOR ALL NATURAL AND PAVED AREAS. 3. CONTRACTOR TO MATCH EXISTING GRADE WITH PROPOSED SIDEWALK ELEVATION. SIDEWALK EDGE DROP-OFFS
- WILL NOT BE ACCEPTED. 4. CONTRACTOR SHALL CONTACT THE ENGINEER REGARDING ANY GRADING REVISIONS PRIOR TO CONSTRUCTION OF
- THE PAVEMENT AREAS.

  5. CONTRACTOR SHALL TAKE FIELD SLOPE MEASUREMENTS ON FINISHED SUBGRADE AND FORM BOARDS PRIOR TO PLACING PAVEMENT TO VERIFY THAT ADA SLOPE REQUIREMENTS ARE PROVIDED. CONTRACTOR SHALL CONTACT ENGINEER PRIOR TO PAVING IF ANY EXCESSIVE SLOPES ARE ENCOUNTERED. NO CONTRACTOR CHANGE ORDERS WILL BE ACCEPTED FOR ADA SLOPE COMPLIANCE ISSUES.
- 6. CLEAN BACKFILL MATERIAL AND MANAGEMENT, EXCEPT WITHIN THE "TREE PROTECTION ZONES" WHERE CONTAMINATED SOIL HAS BEEN PROPOSED TO REMAIN IN-PLACE AND COVERED WITH A 6-MIL OR GREATER
- IMPERMEABLE LINER COVERED BY A MINIMUM OF ONE FOOT OF CLEAN BACKFILL. 7. DOCUMENTATION (RECEIPTS, MANIFEST, ETC.) SHALL BE PROVIDED FROM THE APPLICABLE WASTE DISPOSAL FACILITIES AND MIAMI-DADE COUNTY QUARRY TO DEMONSTRATE THAT ALL CONTAMINATED SOIL WAS PROPERLY DISPOSED AND CLEAN FILL FROM A MIAMI-DADE COUNTY QUARRY WAS USED TO BACKFILL THE SOURCE
- 8. A CONFIRMATION SAMPLING PLAN (CSP) SHALL BE PROVIDED TO DERM UPON COMPLETION OF BACKFILL ACTIVITIES TO VERIFY THE QUALITY OF THE BACKFILL MATERIAL.
  9. CONTRACTOR TO INSTALL TOPSOIL AND ST. AUGUSTINE SOD WITHIN THE ENTIRE PROJECT BOUNDARY, WITH THE EXCEPTION OF THE PROPOSED FLEXI—PAVE WALKWAY.

THE PRESENCE OF GROUNDWATER SHOULD BE ANTICIPATED. CONTRACTOR'S BID SHALL INCLUDE CONSIDERATION FOR ADDRESSING THIS ISSUE AND OBTAINING ALL NECESSARY PERMITS.

ALL ELEVATIONS SHOWN ON THESE PLANS ARI BASED ON THE NGVD 29. TO CONVERT ELEVATIONS TO NAVD 88, SUBTRACT 1.52'.



ALWAYS CALL 811 BEFORE YOU DIG It's fast. It's free. It's the law.

SHEET NUMBER C300.0


OF

RES

Addendum No. 1 Page 14 of 26

www.callsunshine.com


KNOW WHAT'S BELOW



RES

It's fast. It's free. It's the law.

SHEET NUMBER C300.1



5. CONTRACTOR SHALL TAKE FIELD SLOPE MEASUREMENTS ON FINISHED SUBGRADE AND FORM BOARDS PRIOR TO PLACING PAVEMENT TO VERIFY THAT ADA SLOPE REQUIREMENTS ARE PROVIDED. CONTRACTOR SHALL CONTACT ENGINEER PRIOR TO PAVING IF ANY EXCESSIVE SLOPES ARE ENCOUNTERED. NO CONTRACTOR CHANGE ORDERS



SHEET NUMBER C300.2


U

NOL


RESTORA

CUTLE

OF.



SHEET NUMBER C300.3



THE PRESENCE OF GROUNDWATER SHOULD BE ANTICIPATED. CONTRACTOR'S BID SHALL INCLUDE CONSIDERATION FOR ADDRESSING THIS ISSUE AND OBTAINING ALL NECESSARY PERMITS.

ALL ELEVATIONS SHOWN ON THESE PLANS ARE BASED ON THE NGVD 29. TO CONVERT ELEVATIONS TO NAVD 88, SUBTRACT 1.52'.



www.callsunshine.com

SHEET NUMBER C300.4


SECTIONS

**CROSS** 

CUTLER

PREP,

TOWN



- 1. TREES SHALL BE LOCATED IN THE FIELD PRIOR TO CONSTRUCTION. 2. WHERE SHOWN ON PLANS, INSTALL ROOT BARRIER ADJACENT TO SIDEWALKS AND CURBS,
- PER MANUFACTURER'S SPECIFICATION.
- 3. INSTALL BIO-BARRIER PER MANUFACTURER'S SPECIFICATION ADJACENT TO SIDEWALKS AND AS SHOWN ON THIS DETAIL IN PROXIMITY TO UNDERGROUND UTILITIES.

ROOT BARRIER NOT TO SCALE

> THE PRESENCE OF GROUNDWATER SHOULD BE ANTICIPATED. CONTRACTOR'S BID SHALL INCLUDE CONSIDERATION FOR ADDRESSING THIS ISSUE AND OBTAINING ALL NECESSARY PERMITS.


ALL ELEVATIONS SHOWN ON THESE PLANS ARI BASED ON THE NGVD 29. TO CONVERT ELEVATIONS TO NAVD 88, SUBTRACT 1.52'.





SHEET NUMBER C301.0


ARED FOR CUTLE!

AEP OFF









OPEN AIR STRUCTURE

FINISHES: STEEL

MANUFACTURER: POLIGON (OR APPROVED EQUAL)

URL: POLIGON.COM/STEEL ESTIMATED QUANTITY: 2

INSTALLATION: PER MANUFACTURER'S SPECIFICATION NOTES: CONTRACTOR TO PROVIDE AND INSTALL

FABRICATION AND PERMITTING NOTES:

1. DRAWING SHOWN ON THIS SHEET IS FOR INFORMATIONAL PURPOSES ONLY FOR PERMIT REVIEWER'S DISPLAY OF THE GENERAL SCOPE, SIZE, AND SHAPE OF THE PAVILIONS. ENGINEERING DESIGN AND PERMITTING ASSOCIATED WITH THE INSTALLATION AND CONSTRUCTION

SHALL BE PROVIDED BY THE PAVILION FABRICATOR AND CONTRACTOR.

2. CONTRACTOR SHALL PREPARE THE PAVILION SITE AND POUR THE STRUCTURAL FOUNDATION, AS WELL AS ASSEMBLE AND INSTALL THE

PAVILION, PER FABRICATOR'S SPECIFICATIONS. 3. COLOR SHALL BE SELECTED BY THE OWNER. ANTICIPATE TWO COLORS, ONE FOR THE FRAME, AND A SECOND COLOR FOR THE ROOF.

SUBMIT PAINT COLOR CHIPS/SAMPLES TO OWNER FOR COLOR SELECTION.

7. CONTRACTOR TO COORDINATE ANCHORING TYPE WITH THE MANUFACTURER OF THE PAVILION.

PREPARE SLAB WITH MIN. 8" COMPACTED SAND, GRAVEL, OR CRUSHED ROCK.

2. CONCRETE SLAB TO BE 4" THICK. REINFORCE SLAB WITH 6X6-W1.4XW1.4 WELDED WIRE FABRIC AT MID-DEPTH. LAP SPLICES 8". ALT.: FIBER MESH ADMIXTURE (MIN. 1.5#/C.Y., FIBRILLATED POLYPROPYLENE).

3. EDGE OF SLAB TO BE THICKENED TO MIN. 8" DEEP X 8" WIDE REINFORCED WITH 2-#4 CONTINUOUS REBARS. LAP SPLICES MIN. 24".

. INSTALL CRACK CONTROL JOINTS (3/16" WIDE X 1" DEEP) AT 8' TO 12' O.C.
. CONCRETE SLABS IN OPEN AREAS ARE TO BE SLOPED FOR DRAINAGE FROM CENTER TO EDGE AND AWAY FROM COLUMNS. SURFACE IS

TO BE LIGHTLY BROOMED OR HAVE A WOOD TROWELED FINISH. 6. CONCRETE SLAB, FOUNDATION, RE-BAR, WIRE MESH, LEVELING NUTS, GROUT & ANCHOR BOLTS SHALL BE PROVIDED BY CONTRACTOR. ITB No. 25-06

SOIL REMEDIATION PROJECT FOR BLUE HERON PARK Addendum No. 1 Page 20 of 26

ANTICIPATED. CONTRACTOR'S BID SHALL INCLUDE CONSIDERATION FOR ADDRESSING THIS ISSUE AND OBTAINING ALL NECESSARY PERMITS. ALL ELEVATIONS SHOWN ON THESE PLANS ARE BASED ON THE NGVD 29. TO CONVERT

THE PRESENCE OF GROUNDWATER SHOULD BE

ELEVATIONS TO NAVD 88, SUBTRACT 1.52'.

KNOW WHAT'S BELOW ALWAYS CALL 811 BEFORE YOU DIG

It's fast. It's free. It's the law. www.callsunshine.com

SHEET NUMBER C301.1




CUTLER PREP, TOWN

SHEET NUMBER

C301.2

ANTICIPATED. CONTRACTOR'S BID SHALL INCLUDE CONSIDERATION FOR ADDRESSING THIS ISSUE AND OBTAINING ALL NECESSARY PERMITS. ALL ELEVATIONS SHOWN ON THESE PLANS ARE BASED ON THE NGVD 29. TO CONVERT ELEVATIONS TO NAVD 88, SUBTRACT 1.52'.

THE PRESENCE OF GROUNDWATER SHOULD BE




ITB No. 25-06 SOIL REMEDIATION PROJECT FOR BLUE HERON PARK Addendum No. 1 Page 22 of 26


It's fast. It's free. It's the law.

www.callsunshine.com


SHEET NUMBER L1.00



Addendum No. 1 Page 23 of 26



SHEET NUMBER



Tree #	Common Name	Scientific Name	Canopy Diameter	CT (ft.)	DBH (in.)	TPZ (ft.)	Health Condition	Disposition	Tree #	Common Name	Scientific Name	Canopy Diameter	CT (ft.)	DBH (in.)	TPZ (ft.)	Health Condition	Disposition	Tree #	Common Name	Scientific Name	Canopy Diameter	CT (ft.)	DBH (in.)	TPZ (ft.)	Health Condition	Disposition
1	Royal Palm	Roystonea regia	(ft.)	22	. ,	12 ft.	Good	REMAIN	101	Cabbage Palm	Sabal palmetto	(ft.)	31	. ,	12 ft.	Good	REMAIN	201	Cabbage Palm	Sabal palmetto	(ft.)	22	, ,	12 ft.	Good	REMAIN
3	Magnolia Magnolia	magnolia grandiflora magnolia grandiflora				12 ft. 12 ft.	Poor Good	REMAIN REMAIN	102 103	Live Oak Live Oak	Quercus virginiana Quercus virginiana	40 40		22 18	40 ft. 40 ft.	Good Good	REMAIN REMAIN	202 203	Cabbage Palm Cabbage Palm	Sabal palmetto Sabal palmetto		22 22		12 ft. 12 ft.	Good Good	REMAIN REMAIN
4	Magnolia Royal Palm	magnolia grandiflora				12 ft. 12 ft.	Good Good	REMAIN REMAIN	104 105	Royal Palm Royal Palm	Roystonea regia Roystonea regia		22 22		12 ft. 12 ft.	Good Good	REMAIN REMAIN	204 205	Royal Palm Royal Palm	Roystonea regia Roystonea regia		25 25		12 ft. 12 ft.	Good Good	REMAIN REMAIN
6	Mahogany	Roystonea regia Swietenia mahagoni				12 ft.	Good	REMAIN	106 107	Royal Palm Royal Palm	Roystonea regia Roystonea regia		22 22		12 ft. 12 ft.	Good Good	REMAIN REMAIN	206 207	Royal Palm Cabbage Palm	Roystonea regia Sabal palmetto		25 20		12 ft. 12 ft.	Good Good	REMAIN REMAIN
7 8	Java Plum Java Plum	Syzygium cumini Syzygium cumini				12 ft. 12 ft.	Good Good	REMAIN REMAIN	108	Royal Palm	Roystonea regia		22		12 ft.	Good	REMAIN	208	Dead Palm	,				12 ft.	Dead	DEAD
9	Bald Cypress	Taxodium distichum				12 ft.	Good	REMAIN	109 110	Royal Palm Royal Palm	Roystonea regia Roystonea regia		22 22		12 ft. 12 ft.	Good Good	REMAIN REMAIN	209 210	Cabbage Palm Royal Palm	Sabal palmetto Roystonea regia		20 25		12 ft. 12 ft.	Good Good	REMAIN REMAIN
10 11	Bald Cypress Bald Cypress	Taxodium distichum Taxodium distichum				12 ft. 12 ft.	Good Good	REMAIN REMAIN	111 112	Unknown Unknown					12 ft. 12 ft.	poor	REMAIN REMAIN	211 212	Royal Palm Cabbage Palm	Roystonea regia Sabal palmetto		25 25		12 ft. 12 ft.	Good Good	REMAIN REMAIN
12	Gumbo Limbo	Bursera simaruba				12 ft.	Good	REMAIN	113	Unknown	Devetence regio		22		12 ft. 12 ft.	poor	REMAIN REMAIN	213	Cabbage Palm	Sabal palmetto		25 25		12 ft. 12 ft.	Good Good	REMAIN REMAIN
13 14	Gumbo Limbo Gumbo Limbo	Bursera simaruba Bursera simaruba				12 ft. 12 ft.	Good Good	REMAIN REMAIN	114 115	Royal Palm Royal Palm	Roystonea regia Roystonea regia		23		12 ft.	Good Good	REMAIN	214 215	Cabbage Palm Dead Palm	Sabal palmetto		25		12 ft.	Dead	DEAD
15	Gumbo Limbo	Bursera simaruba				12 ft.	Good	REMAIN	116 117	Royal Palm Live Oak	Roystonea regia  Quercus virginiana	50	24	30	12 ft. 50 ft.	Good Good	REMAIN REMAIN	216 217	Royal Poinciana Royal Poinciana	Delonix regia Delonix regia	6		6	12 ft. 12 ft.	Good Good	REMAIN REMAIN
16 17	unknown unknown		15 17		15 17	15 ft. 17 ft.	Good Good	REMAIN REMAIN	118 119	Cabbage Palm Cabbage Palm	Sabal palmetto Sabal palmetto		20 20		12 ft. 12 ft.	Good Good	REMAIN REMAIN	218 219	Royal Palm Royal Palm	Roystonea regia Roystonea regia		25 25		12 ft. 12 ft.	Good Good	REMAIN REMAIN
18	Live Oak	Quercus virginiana	20		12	20 ft.	Good	REMAIN	120	Cabbage Palm	Sabal palmetto		20		12 ft.	Good	REMAIN	220	Royal Poinciana	Delonix regia	27	25	18	27 ft.	Good	REMAIN
19 20	Live Oak Live Oak	Quercus virginiana Quercus virginiana			15 18	12 ft. 12 ft.	Good Good	REMAIN REMAIN	121 122	Cabbage Palm Cabbage Palm	Sabal palmetto Sabal palmetto		20		12 ft. 12 ft.	Dead Good	DEAD REMAIN	221 222	Royal Poinciana Royal Poinciana	Delonix regia Delonix regia	14 25		18 18	14 ft. 25 ft.	Good Good	REMAIN REMAIN
21	Live Oak	Quercus virginiana			18	12 ft.	Good	REMAIN	123 124	Coconut Palm Coconut Palm	Cocos nucifera Cocos nucifera		12 12		12 ft. 12 ft.	Good Good	REMAIN REMAIN	223 224	Bottlebrush Tree Royal Poinciana	Melaleuca viminalis Delonix regia	15 25		18 22	15 ft. 25 ft.	Good Good	REMAIN REMAIN
22 23	Live Oak Cabbage Palm	Quercus virginiana Sabal palmetto		22	19	12 ft. 12 ft.	Good Good	REMAIN REMAIN	125	Live Oak	Quercus virginiana	4		3	12 ft.	Good	REMAIN	225	Royal Poinciana	Delonix regia	10		12	12 ft.	Poor	REMAIN
24	Cabbage Palm	Sabal palmetto		22		12 ft.	Good	REMAIN	126 127	Coconut Palm Live Oak	Cocos nucifera Quercus virginiana	30	15	12	12 ft. 30 ft.	Good Good	REMAIN REMAIN	226 227	Royal Poinciana Royal Poinciana	Delonix regia Delonix regia	30 20		28 25	30 ft. 20 ft.	Good Good	REMAIN REMAIN
25	Cabbage Palm	Sabal palmetto		22		12 ft. 12 ft.	Good	REMAIN	128 129	Cabbage Palm Live Oak	Sabal palmetto  Quercus virginiana	6	8	4	12 ft. 12 ft.	Good Good	REMAIN REMAIN	228 229	Royal Poinciana Royal Poinciana	Delonix regia Delonix regia	25 6		25 20	25 ft. 12 ft.	Good poor	REMAIN REMAIN
26 27	Cabbage Palm Cabbage Palm	Sabal palmetto Sabal palmetto		22 22		12 ft.	Good Good	REMAIN REMAIN	130	Coconut Palm	Cocos nucifera				12 ft.	bent trunk	REMAIN	230	Banyan Tree	Ficus benghalensis	30	25	20	30 ft.	Good	REMAIN
28	Royal Palm	Roystonea regia		22		12 ft.	Good	REMAIN	131 132	Live Oak Coconut Palm	Quercus virginiana Cocos nucifera	4	15	4	12 ft. 12 ft.	Good Good	REMAIN REMAIN	231 232	Royal Palm Royal Palm	Roystonea regia Roystonea regia		25 25		12 ft. 12 ft.	Good Good	REMAIN REMAIN
29 30	Royal Palm Royal Palm	Roystonea regia Roystonea regia		22 22		12 ft. 12 ft.	Good Good	REMAIN REMAIN	133 134	Royal Poinciana Bottlebrush Tree	Delonix regia Melaleuca viminalis	50 12		28 12	50 ft. 12 ft.	Good Good	REMAIN REMAIN	233 234	Banyan Tree Banyan Tree	Ficus benghalensis Ficus benghalensis	35 40		35 38	35 ft. 40 ft.	Good Good	REMAIN REMAIN
31	Royal Palm	Roystonea regia		22		12 ft.	Good	REMAIN	135	Bottlebrush Tree	Melaleuca viminalis	6		6	12 ft.	Good	REMAIN	235	Royal Palm	Roystonea regia		22		12 ft.	Good	REMAIN
32	Royal Palm Royal Palm	Roystonea regia Roystonea regia		22		12 ft. 12 ft.	Good Good	REMAIN REMAIN	136 137	Bottlebrush Tree Coconut Palm	Melaleuca viminalis Cocos nucifera	18	18	12	18 ft. 12 ft.	Good Good	REMAIN REMAIN	236 237	Royal Palm Royal Palm	Roystonea regia Roystonea regia		22 22		12 ft. 12 ft.	Good Good	REMAIN REMAIN
34	Royal Palm	Roystonea regia		22		12 ft.	Good	REMAIN	138 139	Live Oak Coconut Palm	Quercus virginiana  Cocos nucifera	15	18	16	15 ft. 12 ft.	Good Good	REMAIN REMAIN	238 239	Royal Palm Royal Palm	Roystonea regia Roystonea regia		22		12 ft. 12 ft.	Good Good	REMAIN REMAIN
35 36	Royal Palm Royal Palm	Roystonea regia Roystonea regia		22 22		12 ft. 12 ft.	Good Good	REMAIN REMAIN	140	Bottlebrush Tree	Melaleuca viminalis	10	10	18	12 ft. 12 ft.	Good	REMAIN REMAIN	240	Royal Palm	Roystonea regia		22 22		12 ft.	Good	REMAIN REMAIN
37	Royal Palm	Roystonea regia		22		12 ft.	Good	REMAIN	141 142	Cabbage Palm Cabbage Palm	Sabal palmetto Sabal palmetto		18		12 ft.	Good Good	REMAIN	241 242	Royal Palm Royal Palm	Roystonea regia Roystonea regia		15		12 ft. 12 ft.	Good Good	REMAIN
38 39	Royal Palm Unknown	Roystonea regia	5	22	4	12 ft. 12 ft.	Good Good	REMAIN REMAIN	143 144	Cabbage Palm Cabbage Palm	Sabal palmetto Sabal palmetto		18 18		12 ft. 12 ft.	Good Good	REMAIN REMAIN	243 244	Royal Palm Royal Palm	Roystonea regia Roystonea regia		20 18		12 ft. 12 ft.	Good Good	REMAIN REMAIN
40	Unknown		5		4	12 ft.	Good	REMAIN	145 146	Cabbage Palm	Sabal palmetto	12	18	0	12 ft. 12 ft.	Good Good	REMAIN REMAIN	245 246	Royal Palm Royal Palm	Roystonea regia		18 22		12 ft. 12 ft.	Good Good	REMAIN REMAIN
41 42	Unknown Magnolia	magnolia grandiflora	5 42		4 18	12 ft. 42 ft.	Good Good	REMAIN REMAIN	147	Unknown Live Oak	Quercus virginiana	20		16	20 ft.	Good	REMAIN	247	Royal Palm	Roystonea regia Roystonea regia		20		12 ft.	Good	REMAIN
43	Cabbage Palm	Sabal palmetto		25		12 ft.	Good	REMAIN	148 149	Unknown Mahogany	Swietenia mahagoni	25 14		14 8	25 ft. 14 ft.	Good Good	REMAIN REMAIN	248 249	Royal Palm Royal Palm	Roystonea regia Roystonea regia		22 22		12 ft. 12 ft.	Good Good	REMAIN REMAIN
44 45	Cabbage Palm Cabbage Palm	Sabal palmetto Sabal palmetto		25 25		12 ft. 12 ft.	Good Good	REMAIN REMAIN	150 151	Live Oak Cabbage Palm	Quercus virginiana Sabal palmetto	20	15	14	20 ft. 12 ft.	Good Good	REMAIN REMAIN	250 251	Royal Palm Royal Palm	Roystonea regia Roystonea regia		22 22		12 ft. 12 ft.	Good Good	REMAIN REMAIN
46	Cabbage Palm	Sabal palmetto		25		12 ft.	Good	REMAIN	152	Cabbage Palm	Sabal palmetto		15		12 ft.	Good	REMAIN	252	Royal Palm	Roystonea regia		22		12 ft.	Good	REMAIN
47 48	Cabbage Palm Cabbage Palm	Sabal palmetto Sabal palmetto		25 25		12 ft. 12 ft.	Good Good	REMAIN REMAIN	153 154	Unknown Unknown		15		14	12 ft. 15 ft.	Good Good	REMAIN REMAIN	253 254	Royal Palm Royal Palm	Roystonea regia Roystonea regia		22 22		12 ft. 12 ft.	Good Good	REMAIN REMAIN
49	Cabbage Palm	Sabal palmetto		25		12 ft.	Good	REMAIN	155 156	Live Oak Coconut Palm	Quercus virginiana Cocos nucifera	20	16	20	20 ft. 12 ft.	Good Good	REMAIN REMAIN	255 256	Royal Palm Royal Palm	Roystonea regia Roystonea regia		22 22		12 ft. 12 ft.	Good Good	REMAIN REMAIN
50 51	Live Oak Royal Poinciana	Quercus virginiana  Delonix regia	38 12		24 17	38 ft. 12 ft.	Good Good	REMAIN REMAIN	157	Coconut Palm	Cocos nucifera		16		12 ft.	Good	REMAIN	257	Royal Palm	Roystonea regia		22		12 ft.	Good	REMAIN
52	Royal Poinciana	Delonix regia	15		17	15 ft.	Good	REMAIN	158 159	Coconut Palm Coconut Palm	Cocos nucifera Cocos nucifera		16 16		12 ft. 12 ft.	Good Good	REMAIN REMAIN	258 259	Royal Palm Royal Palm	Roystonea regia Roystonea regia		22		12 ft. 12 ft.	Good Good	REMAIN REMAIN
53 54	Royal Poinciana Royal Poinciana	Delonix regia Delonix regia	16 14		17 17	16 ft. 14 ft.	Good Good	REMAIN REMAIN	160 161	Coconut Palm Coconut Palm	Cocos nucifera Cocos nucifera		16 16		12 ft. 12 ft.	Good Good	REMAIN REMAIN	260 261	Royal Palm Royal Palm	Roystonea regia Roystonea regia		22 22		12 ft. 12 ft.	Good Good	REMAIN REMAIN
55	Magnolia	magnolia grandiflora	10		6	12 ft.	Good	REMAIN	162	Mahogany	Swietenia mahagoni	20		14	20 ft.	Good	REMAIN	262	Royal Palm	Roystonea regia		22		12 ft.	Good	REMAIN
56 57	Magnolia Magnolia	magnolia grandiflora magnolia grandiflora	8 8		8	12 ft. 12 ft.	Good Good	REMAIN REMAIN	163 164	Live Oak Live Oak	Quercus virginiana Quercus virginiana	25 20		20 20	25 ft. 20 ft.	Good Good	REMAIN REMAIN	263 264	Royal Palm Royal Palm	Roystonea regia Roystonea regia		22 22		12 ft. 12 ft.	Good Good	REMAIN REMAIN
58	Bottlebrush Tree	Melaleuca viminalis	8		12	12 ft.	Good	REMAIN	165 166	Unknown Cabbage Palm	Sabal palmetto	4	15	4	12 ft. 12 ft.	Good Good	REMAIN REMAIN	265 266	Royal Palm Royal Palm	Roystonea regia Roystonea regia		22		12 ft. 12 ft.	Good Good	REMAIN REMAIN
59 60	Bottlebrush Tree  Queen Palm	Melaleuca viminalis Syagrus romanzoffiana	6	15	10	12 ft. 12 ft.	Good Good	REMAIN REMAIN	167 168	Unknown	-	4		4	12 ft.	Good	REMAIN	267	Royal Palm	Roystonea regia		22		12 ft.	Good	REMAIN REMAIN
61	Queen Palm	Syagrus romanzoffiana		18		12 ft.	Good	REMAIN	169	Dead Palm Live Oak	Quercus virginiana	30		18	12 ft. 30 ft.	Dead Good	DEAD REMAIN	268 269	Royal Palm Royal Palm	Roystonea regia Roystonea regia		22 22		12 ft. 12 ft.	Good Good	REMAIN
62 63	Queen Palm Queen Palm	Syagrus romanzoffiana Syagrus romanzoffiana		18 18		12 ft. 12 ft.	Good Good	REMAIN REMAIN	170 171	Live Oak Cabbage Palm	Quercus virginiana Sabal palmetto	30	25	16	30 ft. 12 ft.	Good Good	REMAIN REMAIN	270 271	Royal Palm Royal Palm	Roystonea regia Roystonea regia		22		12 ft. 12 ft.	Good Good	REMAIN REMAIN
64	Magnolia	magnolia grandiflora	6		8	12 ft.	Good	REMAIN	172 173	Cabbage Palm Cabbage Palm	Sabal palmetto Sabal palmetto		25 25		12 ft. 12 ft.	Good Good	REMAIN REMAIN	272 273	Royal Palm Royal Palm	Roystonea regia Roystonea regia		22 22		12 ft. 12 ft.	Good Good	REMAIN REMAIN
65 66	Buttonwood Buttonwood	Conocarpus erectus  Conocarpus erectus	3		4	12 ft. 12 ft.	Good Good	REMAIN REMAIN	174	Cabbage Palm	Sabal palmetto		25		12 ft.	Good	REMAIN	274	Royal Palm	Roystonea regia		22		12 ft.	Good	REMAIN
67 68	Buttonwood Gumbo Limbo	Conocarpus erectus Bursera simaruba	3		4	12 ft.	Good Good	REMAIN REMAIN	175 176	Cabbage Palm Cabbage Palm	Sabal palmetto Sabal palmetto		25 25		12 ft. 12 ft.	Good Good	REMAIN REMAIN	275 276	Royal Palm Royal Palm	Roystonea regia Roystonea regia		22 22		12 ft. 12 ft.	Good Good	REMAIN REMAIN
69	Gumbo Limbo Gumbo Limbo	Bursera simaruba	4		4	12 ft.	Good	REMAIN	177 178	Cabbage Palm Cabbage Palm	Sabal palmetto Sabal palmetto		25 25		12 ft. 12 ft.	Good Good	REMAIN REMAIN	277 278	Royal Palm Royal Palm	Roystonea regia Roystonea regia		22 22		12 ft. 12 ft.	Good Good	REMAIN REMAIN
70 71	Gumbo Limbo Gumbo Limbo	Bursera simaruba Bursera simaruba	4		4	12 ft. 12 ft.	Good Good	REMAIN REMAIN	179	Cabbage Palm	Sabal palmetto		25 25		12 ft.	Good	REMAIN REMAIN	279	Royal Palm	Roystonea regia		22		12 ft. 12 ft.	Good	REMAIN REMAIN
72	Gumbo Limbo	Bursera simaruba	6		6	12 ft.	Good	REMAIN	180 181	Cabbage Palm Unknown	Sabal palmetto		20		12 ft. 12 ft.	Good Good	REMAIN	280 281	Royal Palm Royal Palm	Roystonea regia Roystonea regia		22		12 ft.	Good Good	REMAIN
73 74	Live Oak Live Oak	Quercus virginiana  Quercus virginiana	22 18		25 25	22 ft. 18 ft.	Good Good	REMAIN REMAIN	182 183	Unknown Unknown					12 ft. 12 ft.	Good Good	REMAIN REMAIN	282 283	Royal Palm Royal Palm	Roystonea regia Roystonea regia		22 22		12 ft. 12 ft.	Good Good	REMAIN REMAIN
75	Live Oak	Quercus virginiana  Quercus virginiana	8		12	12 ft.	Good	REMAIN	184	Cabbage Palm Cabbage Palm	Sabal palmetto Sabal palmetto		25 25		12 ft. 12 ft.	Good Good	REMAIN REMAIN	284 285	Royal Palm Royal Palm	Roystonea regia Roystonea regia		22		12 ft. 12 ft.	Good Good	REMAIN REMAIN
76 77	Live Oak Coconut Palm	Quercus virginiana  Cocos nucifera	30	15	25	30 ft. 12 ft.	Good Good	REMAIN REMAIN	186	Cabbage Palm	Sabal palmetto		25		12 ft.	Good	REMAIN	286	Royal Palm	Roystonea regia		22		12 ft.	Good	REMAIN
78	Coconut Palm	Cocos nucifera		15		12 ft.	Good	REMAIN	187 188	Cabbage Palm Cabbage Palm	Sabal palmetto Sabal palmetto		25 25		12 ft. 12 ft.	Good Good	REMAIN REMAIN	287 288	Royal Palm Royal Palm	Roystonea regia Roystonea regia		22 22		12 ft. 12 ft.	Good Good	REMAIN REMAIN
79 80	Coconut Palm Coconut Palm	Cocos nucifera  Cocos nucifera		15 18		12 ft. 12 ft.	Good Good	REMAIN REMAIN	189 190	Cabbage Palm Buttonwood	Sabal palmetto Conocarpus erectus	17	25	18	12 ft. 17 ft.	Good Good	REMAIN REMAIN	289 290	Royal Palm Royal Palm	Roystonea regia Roystonea regia		22 22		12 ft. 12 ft.	Good Good	REMAIN REMAIN
81	Coconut Palm	Cocos nucifera		18		12 ft.	Good	REMAIN	191	Royal Poinciana	Delonix regia	60		30	60 ft.	Good	REMAIN	291	Royal Palm	Roystonea regia		22		12 ft.	Good	REMAIN
82 83	Coconut Palm Coconut Palm	Cocos nucifera Cocos nucifera		18 12		12 ft. 12 ft.	Good Good	REMAIN REMAIN	192 193	Gumbo Limbo Gumbo Limbo	Bursera simaruba Bursera simaruba	5 4		4	12 ft. 12 ft.	Good Good	REMAIN REMAIN	292 293	Royal Palm Royal Palm	Roystonea regia Roystonea regia		22 22		12 ft. 12 ft.	Good Good	REMAIN REMAIN
84	Coconut Palm	Cocos nucifera		18		12 ft.	Good	REMAIN	194 195	Cabbage Palm Cabbage Palm	Sabal palmetto Sabal palmetto		25 25		12 ft. 12 ft.	Good Good	REMAIN REMAIN	294 295	Royal Palm Royal Palm	Roystonea regia Roystonea regia		22 22		12 ft. 12 ft.	Good Good	REMAIN REMAIN
85 86	Coconut Palm Weeping Willow	Cocos nucifera Salix babylonica	12	18		12 ft. 12 ft.	Good Good	REMAIN REMAIN	196	Cabbage Palm	Sabal palmetto		25		12 ft.	Good	REMAIN	296	Royal Palm	Roystonea regia		22		12 ft.	Good	REMAIN
87	Magnolia	magnolia grandiflora	12		6	12 ft.	Good	REMAIN	197 198	Cabbage Palm Cabbage Palm	Sabal palmetto Sabal palmetto		25 20		12 ft. 12 ft.	Good Good	REMAIN REMAIN	297 298	Royal Palm Royal Palm	Roystonea regia Roystonea regia		22 22		12 ft. 12 ft.	Good Good	REMAIN REMAIN
88 89	Magnolia Magnolia	magnolia grandiflora magnolia grandiflora	12 12		8 6	12 ft. 12 ft.	Good Good	REMAIN REMAIN	199 200	Cabbage Palm Gumbo Limbo	Sabal palmetto Bursera simaruba	6	25	6	12 ft. 12 ft.	Good Good	REMAIN REMAIN	299 300	Royal Palm Royal Palm	Roystonea regia		22 22		12 ft. 12 ft.	Good Good	REMAIN REMAIN
90 91	Royal Poinciana Royal Poinciana	Delonix regia Delonix regia	15 8		14 12	15 ft. 12 ft.	Good Poor	REMAIN REMAIN	200	Campo Lillipo	มนเจต a จแบสเนมส	ı u		U	14 ft.		INCININI	300	1 NO yai Fallif	Roystonea regia		22		14 II.	Joou	INFINITIN
92	Royal Poinciana	Delonix regia	10	40	12	12 ft.	Good	REMAIN																		
93 94	Coconut Palm Royal Poinciana	Cocos nucifera Delonix regia	6	10	10	12 ft. 12 ft.	Good Poor	REMAIN REMAIN																		
95 96	Cabbage Palm Cabbage Palm	Sabal palmetto Sabal palmetto		30 30		12 ft. 12 ft.	Good Good	REMAIN REMAIN																		
97 98	Cabbage Palm Cabbage Palm	Sabal palmetto		30 30		12 ft. 12 ft.	Good Good	REMAIN REMAIN																		
99	Cabbage Palm	Sabal palmetto Sabal palmetto		30		12 ft.	Good	REMAIN																		
100	Cabbage Palm	Sabal palmetto		30		12 ft.	Good	REMAIN																		

CT (ft.): CLEAR TRUNK; MEASURED IN FEET TPZ (ft.): TREE PROTECTION ZONE; MEASURED IN FEET

DBH (in.): DIAMETER AT BREAST HEIGHT; MEASURED IN INCHES

**ELEVATION** 

REFER TO PLANS

<u>PLAN VIEW</u>

CONNECTION

6'H "PERIMETER PLUS" CONSTRUCTION FENCE BY CONWED PLASTICS OR OWNER'S REPRESENTATIVE

24" BURIAL BELOW GRADE.

② 8' TALL METAL "T" POSTS OR 2" x 2" X 8' PRESSURE TREATED WOOD POSTS WITH

FOR APPROVAL PRIOR TO INSTALLATION.

APPROVED EQUAL. SUBMIT PRODUCT INFORMATION

INSTALLATION NOTES:

A. POST SELECTION SHOULD BE BASED ON EXPECTED STRENGTH NEEDS AND THE LENGTH OF TIME FENCE WILL BE IN PLACE. FLEXIBLE FIBERGLASS ROD POSTS ARE RECOMMENDED FOR PARKS, ATHLETIC EVENTS AND CROWD CONTROL INSTALLATIONS. METAL "T" POSTS OR TREATED WOOD POSTS ARE TYPICALLY USED FOR CONSTRUCTION AND OTHER APPLICATIONS.

B. POSTS SHOULD BE DRIVEN INTO THE GROUND TO A DEPTH OF 1/4 OF THE HEIGHT OF THE POST. FOR EXAMPLE, A 8' POST SHOULD BE SET AT LEAST 2' INTO THE GROUND.

C. SPACE POSTS EVERY 6' (MIN.) TO 8' (MAX.).

D. SECURE FENCING TO POST WITH NYLON CABLE TIES (AVAILABLE FROM CONWED PLASTICS). WOOD STRIPS MAY BE ALSO BE USED TO PROVIDE ADDITIONAL SUPPORT AND PROTECTION BETWEEN TIES AND POSTS.

NOTE: IF WIRE TIES ARE USED, AVOID DIRECT CONTACT WITH FENCE. WIRE MAY DAMAGE FENCE OVER TIME.

Tree/Palm Protector / Barrier Detail

CORNER

CONNECTION

TREE DISPOSITION SUMMARY	
TOTAL TREES TO REMAIN	109
TOTAL PALMS TO REMAIN	187
TOTAL TREES TO BE REMOVED	0
TOTAL PALMS TO BE REMOVED	0
TOTAL TREES TO BE RELOCATED	0
TOTAL PALMS TO BE RELOCATED	0
TOTAL DEAD PALMS TO BE REMOVED	4

THE PRESENCE OF GROUNDWATER SHOULD BE ANTICIPATED. CONTRACTOR'S BID SHALL INCLUDE CONSIDERATION FOR ADDRESSING THIS ISSUE AND OBTAINING ALL NECESSARY PERMITS.

ALL ELEVATIONS SHOWN ON THESE PLANS ARE BASED ON THE NGVD 29. TO CONVERT ELEVATIONS TO NAVD 88, SUBTRACT 1.52'.



KNOW WHAT'S BELOW ALWAYS CALL 811 BEFORE YOU DIG

ITB No. 25-06 SOIL REMEDIATION PROJECT FOR BLUE HERON PARK Addendum No. 1 Page 26 of 26

PARK

SITION

DISPO! PLAN

SHEET NUMBER